

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Westerberg Drilling, Inc.
36728 S. Kropf Rd.
Molalla, OR 97038

WELL I.D. # L 71438
START CARD # 170224

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number _____
Name Rocky Mountain Nursery
Address 6880 Corvallis Rd.
City Independence State OR Zip 97351

(2) TYPE OF WORK New Well
 Deepening Alteration (repair/recondition) Abandonment Conversion

(3) DRILL METHOD
 Rotary Air Rotary Mud Cable Auger Cable Mud
 Other _____

(4) PROPOSED USE
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other _____

(5) BORE HOLE CONSTRUCTION Special Construction: Yes No
Depth of Completed Well 75 ft.
Explosives used: Yes No Type _____ Amount _____

BORE HOLE			SEAL			Sacks or Pounds
Diameter	From	To	Material	From	To	
14"	0	23	Bentonite	0	23	28 sacks
10"	23	75				

How was seal placed: Method A B C D E
 Other Bentonite poured & probed

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

Casing:	Diameter	From	To	Gauge	Steel				Plastic				Welded				Threaded			
					✓	□	□	□	□	□	□	□	□	□	□	□	□	□	□	□
10"	+1.5	56	.250																	
Liner:	None																			

Drive Shoe used Inside Outside None
Final location of shoe(s) 56'

(7) PERFORATIONS/SCREENS
 Perforations Method Mills Knife
 Screens Type _____ Material _____

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
28	38	1/4x3	150				

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailer Air Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
100	N/A	60' (air)	1 hr.
200	1'	pump	1 hr.

Temperature of water 56 Depth Artesian Flow Found _____
Was a water analysis done? Yes By whom _____
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
Depth of strata: _____

(9) LOCATION OF WELL (legal description)
County Polk
Tax Lot 1800 Lot _____
Township 8 S Range 4 W WM
Section 33 SW 1/4 NE 1/4

Lat _____ " or _____ (degrees or decimal)
Long _____ " or _____ (degrees or decimal)

Street Address of Well (or nearest address) 6880 Corvallis Rd.
Independence, OR 97351

(10) STATIC WATER LEVEL
18.5 ft. below land surface. Date 11-8-04
_____ ft. below land surface. Date _____
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES
Depth at which water was first found 28'

From	To	Estimated Flow Rate	SWL
28	38	100 gpm	18.5'

(12) WELL LOG Ground Elevation _____

Soil	Material	From	To	SWL
Clay med brown		0	1	18.5
Gravel cemented small		18.5	28	
Sand & gravel grey		28	35	
Large gravel loose		35	38	
Wood-log		38	40	
Cemented gravel		40	45	
Sand grey		45	50	
Clay grey		50	57	
Clay blue grey		57	75	

NOV 26 2004
WATER RESOURCES DEPT
SALEM, OREGON
Date Started 11-4-04 Completed 11-8-04

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number 1358 Date 11-23-04
Signed Byrn B. Steh

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 688 Date 11-2-04
Signed Steven M. Stadler