

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

(START CARD) # 70073

(1) OWNER: Well Number 5-7
Name vern patzlaff
Address 15391 Airlie Rd.
City monmouth State or. Zip 97361

(2) TYPE OF WORK:
☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☐ No Depth of Completed Well 137 ft.
Explosives used ☐ Yes ☐ No Type Amount

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10"	0	58	cement	40	54	3 sak
6"	58	137	rentonite	0	33	11 sak

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other And filled to top with rentonite

Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:
Casing: Diameter 6" From +1 To 58' Gauge 250 Steel ☒ Plastic ☐ Welded ☒ Threaded ☐
Liner: 4" 0 137 160 Steel ☐ Plastic ☒ Welded ☒ Threaded ☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:
☒ Perforations Method SAW CUT
☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
80	135	1/8	53	6" long		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailer ☒ Air ☐ Flowing ☐ Artesian
Yield gal/min Drawdown Drill stem at Time
25 GPM 1 hr.
20 GPM 2 hrs

Temperature of Water 52° Depth Artesian Flow Found
Was a water analysis done? ☐ Yes By whom
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other
Depth of strata:

(9) LOCATION OF WELL by legal description:
County Polk Latitude Longitude
Township 8S N or S Range 5W E or W. WM.
Section 33 SW 1/4 SW 1/4
Tax Lot 608 Lot Block Subdivision
Street Address of Well (or nearest address) Fishback Rd.
Monmouth ore

(10) STATIC WATER LEVEL:
56 ft. below land surface. 2-9-95 Date
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:
Depth at which water was first found

From	To	Estimated Flow Rate	SWL
100	137	20 GPM	

(12) WELL LOG:
Ground elevation

Material	From	To	SWL
Soil	0	1	
yellow sandstone	1	44	
gray sandstone	44	137	

RECEIVED
MAR 12 1995
WATER RESOURCES DEP
SALEM, OREGON
ROBINSON DRILLING
WELLS & PUMPS
4520 Dallas-Salem Hwy.
Salem, Ore. 97304
371-1844

Date started 2-7-95 Completed 2-10-95

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number
Signed Date

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.
WWC Number 13
Signed George Robinson Date