

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

RECEIVED
MAR 30 1970
STATE ENGINEER
SALEM, OREGON

WATER WELL REPORT
STATE OF OREGON
(Please type or print)
(Do not write above this line)

RECEIVED
APR - 6 1970
STATE ENGINEER
SALEM, OREGON

2N/16-11

(1) OWNER:

Name Allen Tom
Address Rufus, Ore

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

12" Diam. from 0 ft. to 29 ft. Gage 102.5
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations	in.	by	in.
perforations from	ft.	to	ft.
perforations from	ft.	to	ft.
perforations from	ft.	to	ft.
perforations from	ft.	to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 150' ft. below land surface Date Feb 26, 70
Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom Columbia Pump
Yield: 430 gal./min. with 240 ft. drawdown after 4 hrs.

Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m. Date
Temperature of water 58° Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Cement
Depth of seal 29' ft.
Diameter of well bore to bottom of seal 15 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☐ Yes ☒ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Sherman Driller's well number 3
1/4 Section 11 T. 2N R. 16E W.M.
Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 8 3/4

Depth drilled 380 ft. Depth of completed well 380 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Soil, Br.	0	5	
Claystone, Gray	5	19	
Basalt, Brown	19	60	
Basalt, Br. Red	60	85	
Basalt, BIK	85	130	
Claystone, Gray	130	135	
Basalt, BIK	135	185	
Basalt, Brown, Red	185	245	
Soil, Br. Kn			
Basalt, Gray	245	315	
Basalt, Broken	315	340	
Flint, Chert			
Basalt, Gray	340	380	

Work started Feb 25 - 1970 Completed Feb 27 1970
Date well drilling machine moved off of well Feb 28 1970

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Don Parry Date Jan 17, 1970
(Drilling Machine Operator)

Drilling Machine Operator's License No. 640

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Project Corporation
(Person, firm or corporation) (Type or print)

Address South 2nd, Walla Walla, Wn.

[Signed] Sam Wescik
(Water Well Contractor)

Contractor's License No. 527 Date 3/24/70