

WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form

WELL ID # L **L70756**(START CARD) # **168525**

(1) OWNER:

Well Number: **2**Name **Buck Hollow Ranch Inc.**Address **Box 2**City **Kent**State **OR** Zip **97033**

(2) TYPE OF WORK:

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☒ Other **Recreat**

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well **180** ft.Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL			Amount
Diameter	From	To	Material	From	To	sacks or pounds
12"	0	110	Bentonite	0	15	7 Bags
8"	110	180	Cement	15	110	40 Bags

How was seal placed: Method ☒ A ☐ B ☐ C ☐ D ☐ E☐ Other

Backfill placed from _____ ft. to _____ ft. Material

Gravel placed from _____ ft. to _____ ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8"	+3.5	110	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	6"	100	180	.250	☒	☐	☒	☐
					☐	☐	☐	☐

Final location of shoe(s) **Cementing Shoe 110 ft.**

(7) PERFORATIONS/SCREENS:

☒ Perforations☐ ScreensMethod **Torch**

Type

Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
120	180	Hole	548	1 1/8"	6"	☐	☒
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
100 +		180	1 hr.

Temperature of Water **57** Depth Artesian Flow foundWas a water analysis done? ☐ Yes By whomDid any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County **Sherman** Latitude **120.77364** Longitude **45.34353**Township **3S** N or S. Range **16E** E or W. of WM.Section **2** NE 1/4 NE 1/4Tax lot **201** Lot Block SubdivisionStreet Address of Well (or nearest address) **92722 Rutledge Rd.****Grass Valley, OR**

(10) STATIC WATER LEVEL:

50 ft. below land surface.Date **10/23/2004**

Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found **155**

From	To	Estimated Flow Rate	SWL
155	179	100+	50

(12) WELL LOG:

Ground elevation **2337**

Material	From	To	SWL
Soil	0	1	
Rock Fract. Med. Grown	1	58	
Clay Yellow Soft	58	92	
Rock Broken Med. Brown W/B	92	103	
Basalt Hard Black	103	123	
Rock Fract. Med. Brown	123	141	
Basalt Fract. Med. Black	141	155	
Rock Fract. Soft Brown W/B	155	179	
Rock Fract. Med. Black	179	180	50

RECEIVED

NOV 02 2004

WATER RESOURCES DEPT
SALEM, OREGONDate started **10/12/2004**Completed **10/23/2004**

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *Charles Austin* WWC Number **790**
Date **10/30/2004**

Charles Austin