

STATE OF OREGON  
WATER WELL REPORT  
(as required by ORS 537.765)

Till  
1307

RECEIVED

MAY 30 1995

35/11w/1dd  
77609

WATER RESOURCES DEPT. (START CARD) #

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Name Boy Scouts of America  
Address 2145 SW Front Ave  
City Portland State Oregon Zip 97201

Well Number 4

(2) TYPE OF WORK

New Well  Deepening  Alteration (repair/recondition)  Abandonment

(3) DRILL METHOD:

Rotary Air  Rotary Mud  Cable  Auger  
 Other

(4) PROPOSED USE:

Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other Scout Camp

(5) BORE HOLE CONSTRUCTION:

Special Construction approval  Yes  No Depth of Completed Well 190 ft.  
Explosives used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE		SEAL				
Diameter	From	To	Material	From	To	Sacks or pounds
10	0	25	Bentonite	0	25	36
6	25	190				

How was seal placed: Method  A  B  C  D  E

Other Placed in dry + prodded

Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6	2	172 1/2	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 172 1/2

(7) PERFORATIONS/SCREENS:

From		To		Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
								<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Flowing Time
40	97	160	2 hr.

Temperature of water 54 Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

SALEM, OREGON

(9) LOCATION OF WELL by legal description:

County Tillamook Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 35 N or S Range 11W E or W. WM. \_\_\_\_\_  
Section 1 SE 1/4 SE 1/4 \_\_\_\_\_  
Tax Lot \_\_\_\_\_ Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) 17500 Cape Lookout Rd.

(10) STATIC WATER LEVEL:

6.3 ft. below land surface. Date 5-23-95  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:

Depth at which water was first found 9

From	To	Estimated Flow Rate	SWL

(12) WELL LOG:

Ground Elevation \_\_\_\_\_

Material	From	To	SWL
Topsoil	0	1	
Brown Clay	1	9	
Brown Clay + Med Gravel, + Fine Black Sand	9	19 1/2	
Gray Clay w/ Fine Sand	19 1/2	164	
Lg + Med Gravel w/ Fine Black Sand	164	190	6.3

Date started 5-20-95 Completed 5-23-95

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number \_\_\_\_\_

Signed \_\_\_\_\_ Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1221

Signed Larry C. Early Date 5-23-95