

S.C.# 0377

RECEIVED

FEB 11 1988

TILL 15/8W-8dc
406

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

(1) OWNER: Well Number: 1
Name E. Alice + Ronald Anderson
Address 15325 S.E. Evergreen Hwy.
City Vancouver State Wash. Zip 98684

(2) TYPE OF WORK:
 New Well Deepen Recondition Abandon

(3) DRILL METHOD
 Rotary Air Rotary Mud Cable
 Other

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Other Restaurant

BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 110 ft.
Explosives used Yes No Type _____ Amount _____

HOLE		SEAL		Amount	
Diameter	From To	Material	From To	sacks	pounds
	0 0 30	Cement	0 30		24
	6 30 110				

How was seal placed: Method A B C D E
 Other _____
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6	71	30	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:	4	20	110	160	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 30

(7) PERFORATIONS/SCREENS:
 Perforations Method Drilled
 Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
0	110		240	4/16	4	<input type="checkbox"/>	<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailer Air Flowing Artesian
Yield gal/min 5 Drawdown 85 Drill stem at 105 Time 1 hr.

Temperature of water 54 Depth Artesian Flow Found _____
Was a water analysis done? Yes By whom _____
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Tillamook Latitude _____ Longitude _____
Township 15 N or S, Range 8W E or W, WM.
Section 8 SW 1/4 SE 1/4
Tax Lot 900 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 17345 Wilson River Hwy., Tillamook, Ore.

(10) STATIC WATER LEVEL:
20 ft. below land surface. Date 1-20-88
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 4

From	To	Estimated Flow Rate	SWL
4	6	1	
80	110	5	

(12) WELL LOG: Ground elevation _____

Material	From	To	SWL
Topsoil	0	1	
Brown Clay	1	6	
Brown Clay + Sm. Boulders	6	23	
Gray Claystone	23	49	
Gray Claystone + Fine Gravel	49	74	
Gray Claystone + Med. Gravel	74	110	

Date started 1-19-88 Completed 1-20-88

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.
Signed Jerry C Every WWC Number 1221
Date 1-20-88

004

NO 0377
RECEIVED

"START CARD"
NOTICE OF BEGINNING OF WELL CONSTRUCTION
(as required by ORS 537.762)

JAN 25 1988

WATER RESOURCES DEPT
SALEM, OREGON

This form must be completed, signed by both the owner (or authorized agent) and constructor, and the original delivered to the Water Resources Department prior to commencement of construction, alteration or abandonment of each well.

Owner's Name and Mailing Address E. Alice Anderson / Ronald C Anderson
15325 S.E. Evergreen Hwy.
Vancouver, Wash. 98684

Proposed Commencement Date 1-18-88

Proposed Well Depth 300, Diameter 6

and Use:

- Domestic
- Thermal
- Community
- Injection
- Industrial
- Other Restaurant
- Irrigation

Proposed Well Location: County Tillamook

Township 1 S (N or S) Range 8 W (E or W) Section 8

At least 2 of these must be provided

1. SW 1/4 of SE 1/4 of above section
2. street address of well location 17345 Wilson River Hwy.
Tillamook, Ore.
3. tax lot number of well location 900
4. attach approved map with location identified.
(see reverse of this form for approved maps)

We hereby certify that we have read the back of this form, and that to the best of our knowledge the information provided herein is accurate and the well is being properly located from septic tanks and septic drain fields.

Ronald C Anderson
~~Larry C Evey~~
Owner's Signature

Larry C Evey
Bonded Water Well Constructor

Owners
Title
1-16-88
Date

License No. 1221
Company Larry Evey Well Drilling Inc.

Note: This is not a Water Right application. The owner is responsible for obtaining a Water Right through the Water Resources Department if required.

RECEIVED JAN 20 1988