

TILL 50068

RECEIVED

STATE OF OREGON WATER SUPPLY WELL REPORT

AUG 15 1996 WELL I.D.# L01426

(START CARD) # 86755

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number Name FOREST RIDGE PROPERTIES Address 9455 KILCHIS RIVER RD City TILLAMOOK State OR Zip 97141

(2) TYPE OF WORK [X] New Well [] Deepening [] Alteration (repair/recondition) [] Abandonment

(3) DRILL METHOD: [X] Rotary Air [] Rotary Mud [] Cable [] Auger [] Other

(4) PROPOSED USE: [X] Domestic [] Community [] Industrial [] Irrigation [] Thermal [] Injection [] Livestock [] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval [] Yes [X] No Depth of Completed Well 89 ft. Explosives used [] Yes [X] No Type Amount

Table with columns: HOLE Diameter, From, To, Material, SEAL From, To, Sacks or pounds. Row 1: 10", 0, 20, Bentonite, 0, 20, 11 SKS. Row 2: 6", 20, 89

How was seal placed: Method [] A [] B [] C [] D [] E [X] Other Poured into annular Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 6", +1, 88, .250, [X], [], [X], []

(7) PERFORATIONS/SCREENS: Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. (This section is crossed out with a diagonal line)

(8) WELL TESTS: Minimum testing time is 1 hour [] Pump [] Bailer [X] Air [] Artesian Flowing Yield gal/min 60 Drawdown Drill stem at 88 Time 1 hr. Temperature of water 54°F Depth Artesian Flow Found

Was a water analysis done? [X] Yes By whom AMJ Did any strata contain water not suitable for intended use? [] Too little [] Salty [] Muddy [] Odor [] Colored [] Other Depth of strata:

(9) LOCATION OF WELL by legal description: County TILLAMOOK Latitude Longitude Township 1N N or S Range 9W E or W. WM. Section 32 SE 1/4 SW 1/4 Tax Lot 600/1100 Block Subdivision Street Address of Well (or nearest address) 9455 KILCHIS RIVER RD BAY CITY, OR

(10) STATIC WATER LEVEL: 18 ft. below land surface. Date 08/09/96 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Depth at which water was first found 85

Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 85, 89, 60 GPM, 18

(12) WELL LOG: Ground Elevation

Table with columns: Material, From, To, SWL. Rows: Topsoil (0-2), Gray gravel (2-29), Gray claystone (29-34), Brown gravel & sand (34-83), Gray-brown basalt, broken (83-85), Hard gray basalt (85-89)

Date started 08/07/96 Completed 08/09/96

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief. Signed Mel Bigsby WWC Number 1492 Date 08/12/96

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief. Signed [Signature] WWC Number 573 Date 08/12/96