

WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

Instructions for completing this report are on the back of this form.

MAR 13 2000

T.O.L.

506.77

WELL ID # L-38892

(START CARD) # 122675

Corrected by (WAW) 12-19-00

(1) OWNER:

SALEM, OREGON
 Name Silver Valley Mobile Park Water District
 Address 3330 Center St NE
 City Salem State OR Zip 97301

(2) TYPE OF WORK:

X New Well Deepening Alteration (repair/recondition) Abandonment

(3) DRILL METHOD:

X Rotary Air Rotary Mud X Cable Auger
 Other

(4) PROPOSED USE:

Domestic Thermal X Community Injection Industrial Livestock Irrigation Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes X No Depth of Completed Well 430 ft
 Explosives used Yes X No Type Amount

Diameter	From	To	Material	SEAL		From	To	Amount
				sacks	or pounds			
10 in	0	54	cement			0	205	39 sacks
8 in	54	205						
6 in	205	430						

How was seal placed: Method A X B X C D E

Other Backfill placed from ft. to ft. Material
 Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Casing	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
	6 in	+2	205	.250	X		X	
Liner	5 in	10	430	.256	X			X

Final location of sheets) 205 ft 6 Inch, 430 ft 5 Inch

(7) PERFORATIONS/SCREENS:

X Perforations Method torch Material
 Screens Type
 From To Slot Number Diameter Tele/pipe Casing Liner
 355 420 1/8 60 5 5 X

(8) WELL TESTS: Minimum testing time is 1 hour

X Pump X Bailer X Air Flowing Artesian
 Yield gpm Drawdown Drill stem at Time
 11 gpm 175 ballertest 1 hr
 15 gpm air 425 1 hr
 1 hr.

Temperature of Water: 54 deg f Depth Artesian Flow found
 Was a water analysis done? Yes By whom
 Did any slats contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored X Other shallows
 Depth of slate: 37-47 ft

ORIGINAL & FIRST COPY - WATER RESOURCES DEPARTMENT SECOND COPY - CONSTRUCTOR THIRD COPY - CUSTOMER

DEC 20 2000

WATER RESOURCES DEPT.
 SALEM, OREGON

(9) LOCATION OF WELL by legal description:

County Tillamook Latitude Longitude
 Township 6S Nor S. Range 10W E or W. of WM
 Section 9 SE Block 114 SW 114
 Tax lot 4400 Lot Block Subdivision
 Street Address of Well (or nearest address) South End of cascade
 terrace rd Silver valley mobile ranch

(10) STATIC WATER LEVEL:

38 ft below land surface. Date 1-19-00
 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 37 ft

From	To	Estimated Flow Rate	SWL
37	47	3 gpm	5
350	405	15 gpm	38

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
Clay Brown and Boulders	0	27	
Clay Grey, Boulders, Broken	27		
Basalt and Claystone		37	
Claystone and Sandstone Grey and White with Basalt Gravel	37	47	5
Claystone Brown with Sandstone and White Claystone Seams	47	95	
Claystone Grey and Sandstone Seams, Crumbly	95	175	175
Claystone Grey Hard	175	310	310
Sandstone Grey and Brown Hard, with Calcite Seams	310	315	315
Claystone Grey Soft Crumbly	315	325	325
Claystone Dark Grey Hard with Sandstone Seams, Light Grey, Brown	325	350	350
Sandstone Light Grey and Blue Fractured W. B.	350	405	405 38
Claystone Grey With Sandstone Seams	405	430	430

Date started 12-6-99 Completed 1-19-00

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number 1454
 Signed *J. M. C.* Date 1-25-00

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Michael Waldberg WWC Number 633
 Date 3-10-00

RECEIVED