

RECEIVED

TILL 51167

JUL 30 2003

STATE OF OREGON
WATER SUPPLY WELL REPORT

WELL I.D. # L 65925
START CARD # 148477

(as required by ORS 537.765)
WATER RESOURCES DEPT
SALEM, OREGON
Instructions for completing this report are on the last page of this form.

(1) LAND OWNER

Name Boy Scouts of America Well Number _____
Address 2145 SW Front Ave
City Portland State Ore Zip 97201

(2) TYPE OF WORK

New Well Deepening Alteration (repair/recondition) Abandonment

(3) DRILL METHOD:

Rotary Air Rotary Mud Cable Auger
 Other _____

(4) PROPOSED USE:

Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other CAMP

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes No Depth of Completed Well 240 ft.
Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
6"	172	240	undisturbed			

How was seal placed: Method A B C D E
 Other _____
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	172	199	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	5"	0	185	#160	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:	5"	215	240	#160	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	5"	230	240	#160	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Drive Shoe used Inside Outside None
Final location of shoe(s) 199'

(7) PERFORATIONS/SCREENS:

Perforations Method Mills Knife
 Screens Type Maas-Egan Material stainless steel

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
165	199	1/2"	210	1/4"	6"	<input checked="" type="checkbox"/>	<input type="checkbox"/>
195	215	.040			5"	<input type="checkbox"/>	<input type="checkbox"/>
220	230	.040			5"	<input checked="" type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump Bailor Air Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
60	150'	240'	14 hr Air
30	5' (to 95')	190'	6 hr Pump

Temperature of water 53° Depth Artesian Flow Found _____
Was a water analysis done? Yes By whom _____
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
Depth of strata: 150'

(9) LOCATION OF WELL by legal description:

County Tillamook Latitude _____ Longitude _____
Township 3 N or S Range 11 E or W M.
Section 1 SE 1/4 SE 1/4
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 17500 Cape Lookout Rd

(10) STATIC WATER LEVEL:

90 ft. below land surface. Date 7-23-03
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 172'

From	To	Estimated Flow Rate	SWL
172	230	60	90

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Sand + Gravel (Coarse)	190	205	90
Fine Sand, clay w/ gravel	205	220	90
Sand + gravel	220	230	90
Sandy Clay (gray)	230	240	90

Dickerson Well Drilling, Inc
ph # 503-623-2664

Date started 6-23-03 Completed 7-23-03

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1571
Signed William A. Klein Date 7-24-03