

DATE	FROM	TO	FORMATION	COMMENTS	SWL	GPM
Jul 13, 1995	0	11	SOIL			
	11	21	1' GRAVEL			
	21	46	BROWN CLAY			
	46	56	2' ROCK & BROWN CLAY			
	56	61	RED & BROWN CLAY			
Jul 20, 1995	61	116	BROWN CLAY & GRAVEL	CAVED IN TO 110 83' OF 12" CASING		
Jul 24, 1995	116	120	GRAY CLAY & GRAVEL	STANDING OPEN TO 122'		
Jul 25, 1995	120	126	BROWN CLAY & GRAVEL			
Jul 25, 1995	126	130	BLACK BASALT			
Jul 31, 1995	130	145	BLACK BASALT			
	145	152	BROWN BASALT	SOFT		
	152	187	BROKEN BROWN BASALT			
	187	197	BLACK BASALT	SCORIA		
	197	222	BLACK BASALT			
	222	240	BROWN BASALT			
	240	250	BLACK BASALT			
8/1-8/3				REPAIR RIG		
Aug 4, 1995	250	280	BLACK BASALT	SOFT		
Aug 7, 1995	280	315	BLACK BASALT	SOFT		
	POSSIBLE PROBLEM @ 207					
	315	349	GRAY BASALT			
Aug 8, 1995	349	355	BROWN BASALT	SOFT		346
Aug 14, 1995	355	368	BLACK BASALT	CEMENT IN 8" FROM 262 TO 368		
	READY MIX M 22074					
	368	372	BLACK BASALT			
	372	376	BLACK BASALT	SCORIA		
Aug 16, 1995	376	385	BLACK BASALT			
	385	389	BLACK BASALT	BROKEN		
	389	404	BLACK BASALT			18
	404	408	RED BASALT	SOFT		
	408	413	BLACK SCORIA & GREEN CLAY STONE			
	413	424	BLACK BASALT			35
	424	438	BLACK BASALT	CAVING	68 F.	75
	438	441	BLACK BASALT			
	441	479	BLACK BASALT	BROKEN, CAVING		H20
	479	523	BLACK BASALT			H20
Aug 17, 1995	BRIDGE 381' TO 390', OPEN BELOW CEMENT FROM 390' TO VARIOUS LEVELS, 8 TIMES					
Jan 21, 1996	523	594	BLACK BASALT			
	594	598	BLACK BASALT			
	598	612	BLACK	HARD		
	612	616	BLACK	SOFT	POSSIBLE H20	
	616	630	BLACK	HARD		
	630	690	BLACK	BROKEN	POSSIBLE H20	
	690	706	BLACK			

RECEIVED

MAR - 7 1996

WATER RESOURCES DEPT.
SALEM, OREGON