

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

RECEIVED SEP 22 1967 STATE ENGINEER

WATER WELL REPORT

STATE OF OREGON

(Please type or print) (Do not write above this line)

UMAT 5065

State Well No. 6N/35-35

35 accd

State Permit No. G-4667

(1) OWNER:

Name City of MILTON-Freeport Address Box 108 - M.F. One

(2) TYPE OF WORK (check):

New Well [X] Deepening [] Reconditioning [] Abandon []

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary [] Driven [] Cable [X] Jetted [] Dug [] Bored []

(4) PROPOSED USE (check):

Domestic [X] Industrial [] Municipal [] Irrigation [] Test Well [] Other []

(5) CASING INSTALLED:

6" Diam. from 1-150 lb. threaded pipe to 108 ft. Gage 280

(6) PERFORATIONS:

Perforated? [X] Yes [] No. Type of perforator used Colling Torch. Size of perforations 4 in. by 4 to 8 in. length. 6.8 perforations from 5.5 ft. to 6.5 ft. 206 perforations from 8.3 ft. to 108 ft.

(7) SCREENS:

Well screen installed? [] Yes [X] No. Manufacturer's Name Type Model No. Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 37 ft. below land surface Date 9/18 Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level. Was a pump test made? [X] Yes [] No. If yes, by whom? Bill Widner. 30 gal./min. with 48 ft. drawdown after 2 hrs. 45 gal./min. with 63 ft. drawdown after 4 hrs. Bailer 50 gal./min. with 63 ft. drawdown after 4 hrs. Artesian flow g.p.m. Date some for the. Temperature of water 58 Was a chemical analysis made? [] Yes [X] No

(10) CONSTRUCTION:

Well seal—Material used Cement. Depth of seal 38 ft. Diameter of well bore to bottom of seal 9 in. Were any loose strata cemented off? [] Yes [X] No Depth. Was a drive shoe used? [X] Yes [] No. Did any strata contain unusable water? [] Yes [X] No. Type of water? depth of strata. Method of sealing strata off. Was well gravel packed? [X] Yes [] No Size of gravel: 3/4-in. Gravel placed from 38 ft. to 80 ft.

(11) LOCATION OF WELL:

County Umatilla Driller's well number 1/4 Section 36 T. 6N. R. 35E. W.M.

Bearing and distance from section or subdivision corner on Cobb R. near old Millway

(12) WELL LOG:

Diameter of well below casing 6" Depth drilled 153 ft. Depth of completed well 153 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

Table with columns: MATERIAL, From, To, SWL. Rows include: Brown soil + gravel (0-3), Brown silty soil + gravel (3-5), Cobbles + gravel (5-11), Brown hard pan (11-14), Gray cemented gravel (14-50) water, Water bearing gr. (50-53), Brown hard pan (53-57), Brown pocket clay + gr. (67-79) water, Brown clay softer (79-109) water, Brown clay pocket hard (109-115), CLAY Bratin pocket hard (115-122) water, Clay Brown coarse sand hard (122-130), 3" of water bearing gravel (130-132), 364' in (130-130), Clay Brown pocket, fine gr. (130-146) water, 3" layer of gravel (146-146), Clay Brown pocket hard (146-153), Larger layer of gravel (153-153) water.

Work started 9/6 1967 Completed 9/19 1967 Date well drilling machine moved off of well 19 1967

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Rudd W. Davis Date 9/19 1967 (Drilling Machine Operator)

Drilling Machine Operator's License No. 147

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Rudd W. Davis (Person, firm or corporation) (Type or print)

Address 159. So Columbus M.F. One

[Signed] Rudd W. Davis (Water Well Contractor)

Contractor's License No. 159 Date 9/19 1967