

RECEIVED

PAGE 1 of 2

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

MAY 03 1999

WATER RESOURCES DEPT.
SALEM, OREGON

UMAT
53417

WELL I.D. # L 20519

START CARD # 10670

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Well Number L20519

Name Tim Weinke

Address P.O. Box 937

City Bellevue State OR Zip 97145

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☒ Irrigation

☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 74 ft.

Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
12"	0	69'	RET. CEM.	69'	0'	23 SACKS

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E

☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8"	+2	69'	250	☒	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

☐ Perforations

Method _____

☐ Screens

Type _____

Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump

☐ Bailor

☒ Air

☐ Flowing

☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
400+		714	1 hr.
300+		622	
300+		522	

Temperature of water 62° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County UMAT Latitude _____ Longitude _____

Township 1 S N or S Range 32 E or W. WM.

Section 6 SW 1/4 SE 1/4

Tax Lot 2100 Lot _____ Block _____ Subdivision _____

Street Address of Well (or nearest address) _____

(10) STATIC WATER LEVEL:

230 ft. below land surface.

Date 04-19-99

Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 412'

From	To	Estimated Flow Rate	SWL
412'	425'	40 gpm	
540'	590'	300+ gpm	
685'	702'	350+ gpm	
705'	710'	400+ gpm	230'

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
SOIL	0'	6"	
BROKEN BROWN BASALT	6"	27'	
RED W/WHITE	27'	29'	
BROKEN BROWN	29'	56'	
BLACK BASALT	56'	71'	
RED BASALT	71'	75'	
BROWN BASALT	75'	110'	
RED W/WHITE	110'	124'	
BROWN BASALT	124'	149'	
BLACK BASALT	149'	160'	
BROWN W/WHITE	160'	170'	
BLACK BASALT	220'	312'	
BROWN BASALT	312'	350'	
BROWN W/WHITE	350'	370'	
BROWN (GFT)	370'	412'	
BROWN W/WHITE	412'	425'	
BLACK W/GREEN	425'	460'	
BROWN W/WHITE	460'	500'	
BLACK W/GREEN	500'	535'	
BLACK BASALT	535'	540'	

Date started 04-02-99

Completed 04-19-99

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed Robert L. Linton

WWC Number 1731

Date 04-19-99

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Jerry Bunt

WWC Number 544

Date 4-19-99

