

OCT 12 2001

STATE OF OREGON

WATER SUPPLY WELL REPORT WATER RESOURCES DEPT.

(as required by ORS 537.765)

SALEM, OREGON

WELL I.D. # L 21098

START CARD # 143058

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number _____
 Name Helen A Teribury
 Address P.O. Box 462
 City Pilot Rock State OR Zip 971

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:
 Special Construction approval ☐ Yes ☐ No Depth of Completed Well 320 ft.
 Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Sacks or pounds
Diameter	From	To	Material	From	To	
12	0	63	Concrete	53	63	10 Sacks
8	63	320	Ballast	0	53	49 Sacks

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other Portland Cement

Backfill placed from _____ ft. to _____ ft. Material _____
 Gravel placed from _____ ft. to NONE ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 8	0	63	250	☒	☐	☒	☐
Liner:		<u>NONE</u>		☐	☐	☐	☐

Drive Shoe used ☐ Inside ☒ Outside ☐ None
 Final location of shoe(s) 8" 638"

(7) PERFORATIONS/SCREENS:
☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
				<u>NONE</u>		☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Flowing ☐ Artesian Time
<u>300</u>		<u>300</u>	1 hr.

Temperature of water 65 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:
 County Umatilla Latitude _____ Longitude _____
 Township 1N N or S Range 32E E or W. WM.
 Section 27 N1/4 14 1/4
 Tax Lot 6903 Lot _____ Block _____ Subdivision _____
 Street Address of Well (or nearest address) Off Hoot Rd
Pendleton OR

(10) STATIC WATER LEVEL:
98 ft. below land surface. Date 10-9-2001
 Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:
 Depth at which water was first found 315

From	To	Estimated Flow Rate	SWL
315	320	300	98

(12) WELL LOG:
 Ground Elevation _____

Material	From	To	SWL
Sandy Soil	0	7	
Brown Sandy Clay	7	23	
Clay Gravel Sand	23	54	
Black Basalt	54	95	
Vertical Brown Basalt	95	115	
Black Basalt	115	130	
Vertical Brown Basalt	130	140	
Black Basalt Blocky	140	180	
Black Basalt	180	215	
Vertical Black Clay	215	230	
Vertical Brown Sand	230	245	
Fractured Black Basalt	245	290	
Grey Basalt (Hard)	290	315	
Couise Redstart Rock	315	320	98
4/8			

Date started 10-2-2001 Completed 10-9-2001

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed Michael J. K WWC Number 1737 Date 10-9-2001

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Robert J. Stafford WWC Number 415 Date 10-10-2001