

RECEIVED Page 1 of 2

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 670.005)

Instructions for completing this report are on the last page of this form.

UMAT
54794WELL I.D. # L 43422
START CARD # 127930

(1) LAND OWNER

Well Number _____

Name LARRY APPLEATE
Address 77468 CAMPBELL ROAD
City PENDLETON State OREGON Zip 97801

(2) TYPE OF WORK

☐ New Well ☒ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 1220 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Sacks or pounds
Diameter	From	To	Material	From	To	
6"	424	1220	Port Cement	424	410	5 Sacks

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other _____Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	424	424	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Drive Shoe used ☐ Inside ☐ Outside ☐ None

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
		N/A				☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing ☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
30 gpm		1220	1 hr.
20 gpm		1020	
20 gpm		820	

Temperature of water 68° Depth Artesian Flow Found _____Was a water analysis done? ☐ Yes By whom _____Did any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Umatilla Latitude _____ Longitude _____
Township 4 ☐ or S Range 32 ☐ or W. WM.
Section 35 ☐ 1/4 D 1/4
Tax Lot 7821 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 77468 CAMPBELL RD.
PENDLETON, OREGON 97801

(10) STATIC WATER LEVEL:

490 ft. below land surface. Date 03-15-01
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found _____

From	To	Estimated Flow Rate	SWL
570	575	10 gpm	
1210	1215	30 gpm	490'

RECEIVED

MAY 19 2003

(12) WELL LOG:

Ground Elevation _____ WATER RESOURCES DEPT
SALEM, OREGON

Material	From	To	SWL
BLACK BASALT	424	495	
BLACK W/BROWN	495	515	
BLACK BASALT	515	570	
BLACK SCORIA	570	575	
BLACK BASALT	575	640	
BROWN BASALT	640	650	
BLACK BASALT	650	765	
RED W/ BROWN CLAYSTONE	765	770	
BROWN BASALT	770	780	
BLACK BASALT	780	795	
BLACK W/ GREEN CLAYSTONE	795	815	
BLACK BASALT	815	835	
BLACK W/ GREEN CLAYSTONE	835	880	
BLACK BASALT	880	910	
BROWN BASALT	910	925	
BLACK BASALT	925	945	
BLACK W/ GREEN CLAYSTONE	945	960	
BLACK BASALT	960	1050	
RED W/ GREEN & WHITE	1050	1060	

Date started 02-09-01 Completed 03-14-01

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed [Signature] WWC Number 1731
Date 03-15-01

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 544
Date 3-15-01

