

WELL LABEL # L 83497

START CARD # 187042

(1) LAND OWNER

Owner Well I.D. _____

First Name RICH Last Name THOMAS

Company _____

Address PO BOX 1253

City PENDLETON State OR Zip 97801

(2) TYPE OF WORK ☒ New Well ☐ Deepening ☐ Conversion
☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE ☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION Special Standard ☐ (Attach copy)

Depth of Completed Well 517.00 ft.

BORE HOLE			SEAL			Amt	sacks/ lbs
Dia	From	To	Material	From	To		
12	0	18	Bentonite	0	18	14	S
7.5	18	517					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other POURED 3/8 CHIPS

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Yes Type _____ Amount _____

(6) CASING/LINER

Casing	Liner	Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd
☒	☐	8	☒	2	18	.25	☒	☐	☒	☐
☐	☐		☐				☐	☐	☐	☐
☐	☐		☐				☐	☐	☐	☐
☐	☐		☐				☐	☐	☐	☐
☐	☐		☐				☐	☐	☐	☐

Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s) _____

Temp casing ☐ Yes Dia _____ From _____ To _____

(7) PERFORATIONS/SCREENS

Perforations Method _____

Screens Type _____ Material _____

Perf/	Casing/	Screen	Dia	From	To	Scrn/slot	Slot	# of	Tele/
Screen	Liner					width	length	slots	pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem/Pump depth	Duration (hr)
300		517	1
150		427	1
60		327	1

Temperature 63 °F Lab analysis ☐ Yes By _____

Water quality concerns? ☐ Yes (describe below)

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County Umatilla Twp 1.00 N N/S Range 32.00 E E/W WM

Sec 17 SE 1/4 of the NE 1/4 Tax Lot 2200

Tax Map Number _____ Lot _____

Lat _____ ' " or _____ DMS or DD

Long _____ ' " or _____ DMS or DD

☒ Street address of well ☐ Nearest address

69754 GEORGE CANYON RD

(10) STATIC WATER LEVEL

Date SWL(psi) + SWL(ft)

Existing Well / Predeepening			
Completed Well	06-27-2006		260

Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES

Depth water was first found

SWL Date	From	To	Est Flow	SWL(psi)	+ SWL(ft)
06-27-2006	350	365	15		260
06-27-2006	440	460	20		260
06-27-2006	480	505	300		260

(11) WELL LOG

Ground Elevation _____

Material	From	To
SOIL	0	3
BLACK BASALT	3	45
BROWN BASALT	45	105
BLACK BASALT	105	162
BROWN BASALT	162	250
BLACK BASALT	250	275
BLACK BASALT/GREEN CLAYSTON	275	330
BLACK BASALT	330	350
BLACK BASALT/TAN CLAYSTONE	350	365
BLACK BASALT	365	440
BLACK BASALT/GREEN CLAYSTONE	440	460
BLACK BASALT	460	480
BROWN BASALT/TAN CLAYSTONE	480	505
BLACK BASALT	505	517

Date Started 06-26-2006

Completed 06-27-2006

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1735

Date 06-29-2006

Electronically Filed

Signed CHAD COURTNEY (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 544

Date 06-29-2006

Electronically Filed

Signed LARRY BURD (E-filed)

Contact Info (optional)