

UMATILLA 5590

Telephone Call
NE 9 SE 14?
10/15/71 - 2N/33-14CB
6-7
State Well No. 2N/33-32G

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

JUN 8 1966 WATER WELL REPORT

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

STATE OF OREGON ENGINEER (Please type or print)

State Permit No.

(1) OWNER:

Name CITY OF PENDELTON
Address PENDELTON, ORE.

(2) LOCATION OF WELL:

County UMATILLA Driller's well number 4123
SW 1/4 NE 1/4 Section 38 T. 2N R. 33E W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

Well Deepening Reconditioning Abandon
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic Industrial Municipal Rotary Driven
Irrigation Test Well Other Cable Jetted
Dug Bored

(5) TYPE OF WELL:

(6) CASING INSTALLED:

Threaded Welded
12" Diam. from 0 ft. to 157 ft. Gage 330
" Diam. from " ft. to " ft. Gage
" Diam. from " ft. to " ft. Gage

(7) PERFORATIONS:

Perforated? Yes No

Type of perforator used

Size of perforations in. by in.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.

(8) SCREENS:

Well screen installed? Yes No

Manufacturer's Name
Model No.
Diam. Slot size Set from " ft. to " ft.
Diam. Slot size Set from " ft. to " ft.

(9) CONSTRUCTION:

Well seal—Material used in seal CEMENT GROUT
Depth of seal 143-157 ft. Was a packer used? No
Diameter of well bore to bottom of seal in.
Were any loose strata cemented off? Yes No Depth
Was a drive shoe used? Yes No
Was well gravel packed? Yes No Size of gravel:
Gravel placed from " ft. to " ft.
Did any strata contain unusable water? Yes No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 1 ft. below land surface Date 4/21/66
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? Yes No If yes, by whom? STRASSER

Yield: 1000 gal./min. with 175 ft. drawdown after 21 hrs.
" 859 " 165 " 2 "
" 820 " 162 " 1 "

Ballor test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 60 Was a chemical analysis made? Yes No

(12) WELL LOG:

Diameter of well below casing 12 AND 8

Depth drilled 452 ft. Depth of completed well 452 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
TOP SOIL	0	8
GRAVEL AND BOULDERS	8	63
YELLOW BROWN CLAY	63	74
BROWN CLAY	74	85
BROWN SANDY CLAY	85	115
BROWN CLAY AND GRAVEL	115	140
BROKEN ROCK	140	149
BLACK BASALT	149	160
BROWN AND GREY BASALT	160	180
HARD GREY BASALT	180	212
BLACK BASALT	212	230
BROWN LAVA	230	255
BLACK BASALT	255	324
HARD GREY BASALT	324	331
BLACK MED. HARD	331	347
POROUS BLACK ROCK	347	351
MED HARD BLACK BASALT	351	371
HARD BLACK BASALT	371	392
HARD GREY BASALT	392	434
GREY BASALT CREVICES	434	436
GREY BASALT AND CLAY	436	449
GREY BASALT	449	452

Work started 1/13 1966 Completed 4/26 1966
Date well drilling machine moved off of well 4/27 1966

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME R.J. STRASSER DRILLING Co
(Person, firm or corporation) (Type or print)

Address 810 SE SONSET LANE PORTLAND ORE

Drilling Machine Operator's License No. 56 AND 395

[Signed] Robert J. Strasser
(Water Well Contractor)

Contractor's License No. 10 Date MAY 23 1966



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for
Well ID Number

Do not complete if the well already has a Well I.D Number.

I. OWNER INFORMATION

Current Owner Name (please print): City of Pendleton
Mailing Address: 500 SW Dorian Ave.
City: Pendleton State: OR Zip: 97801
Mailing Address (to send Well I.D.):
City: State: Zip:

II. WELL INFORMATION (Do not complete this section if the well report is attached.) Mission Well # 7

Township: 2N (North/South) Range: 33 E (East/West) Section: 14
Tax Lot: 3501 County: Umatilla NW 1/4 SW 1/4
Street Address of Well: 73740 Reservoir Lane City: Pendleton
Owner at time the well was constructed, (if known): City of Pendleton
If the property had a different street address in the past: Old Cabbage Hill Road, Mission

III. GENERAL WELL INFORMATION (Do not complete this section if the well report is attached)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): municipal
Date Well Constructed: 1966 Total Well Depth: 800' Casing Diameter: 12"-157"
Other Information:

SUBMITTED BY (please print): Karen King, Regulatory Specialist, City
PHONE: 541-966-0249 FAX: 541-966-0251

Well ID # L 94960

RECEIVED BY OWRD

MAY 06 2013

Send application to Oregon Water Resources Department; 725 Summer St NE, Suite A; Salem, Oregon 97301-1266; fax (503) 986-0902. Applications are processed and Well I.D. Numbers are mailed every Wednesday.

SALEM, OR

For Official Use Only by the Oregon Water Resources Department:

Received Date: 5-6-13 Well Log Number: UMAT 1006 Deepening Well Identification #: L-94960

UMAT 5590 New (only)