

UMAT 56261

1013 N. Clinton
Walla Walla, Wash.

Telephone
5092

Application U-356
Permit U-325
Cert 83450

D. K. Don Smith
Well Drilling Contractor

Form B indicates well was
completed & June 1, 1950.

Log of Milton Carter Well

<u>Formation</u>	<u>Depth</u>	
Soil	0-10	Feet
Broken Basalt	10-44	"
Grey "	44-64	"
Broken Brown Basalt	64-98	"
Grey basalt	98-102	"
Black basalt	102-114	"
Grey basalt	114-132	"
Black basalt (small amount of water)	132-138	"
Grey basalt	138-144	"
Brown basalt	144-155	"
Grey basalt	155-167	"
Brown basalt	167-199	"
Black basalt	199-213	"
Broken brown basalt (water bearing)	213-229	"

57 feet of 8" casing cemented
Static water level 63 Feet

<u>GPM</u>	<u>PUMPING LEVEL</u>
380	70 Feet
350	68 "
300	67 "
250	65.5 "
200	64.5 "