

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

MAR 15 1993

(START CARD) #

(1) OWNER:

Name Doug I. Brown
Address P.O. Box 339
City Milton-Freewater State Or. Zip 97862

Well Number:

SALEM, OR

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☐ Rotary Air ☐ Rotary Mud ☒ Cable
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 140 ft.
Explosives used ☐ Type XX Amount

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
12	0	30	Port. Cem	0	35	10 sacks

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☒ E
☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6	tl	108	025	☒	☐	☒	☐
Liner:					☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☒ Bailor ☐ Air ☐ Flowing
Yield gal/min 40 Drawdown 0 Drill stem at 1 hr. Time 1 hr.

Temperature of water 48 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☒ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Umatilla Latitude _____ Longitude _____
Township 6-N N or S. Range 35-E E or W. WM.
Section 36-C 1/4 _____ 1/4 _____
Tax Lot 401-E Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) _____

(10) STATIC WATER LEVEL:

32 ft. below land surface. Date 12-5-92
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found _____

From	To	Estimated Flow Rate	SWL
29	32		27
55	80		25
110	140	40gpm	32

(12) WELL LOG:

Material	From	To	SWL
Land fill	0-	10	
Cemented gravel	10	29	
Gravel	29	32	27
Gravel some clay	32	55	
Gravel	55	80	25
Brown clay litt. gravel	80	110	
Gravel little clay	110	140	32
Brown clay	140		

Date started 9-23-92 Completed 12-5-92

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed Shawn D. Parr WWC Number _____ Date 3-11-93

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed Lowell W. Marshall WWC Number 245 Date 3-11-93