

STATE OF OREGON
WATER SUPPLY WELL REPORT

UMAT 59568

WELL I.D. LABEL# L

Page 1 of 3

START CARD #

ORIGINAL LOG #

157162

1082646

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

7/14/2026

(1) LAND OWNER

Owner Well I.D.

First Name ANNA

Last Name TIMPY

Company

Address 82353 MUNGER LN

City UMATILLA

State OR

Zip 97882

(2) TYPE OF WORK

☒ New Well

☐ Deepening

☐ Conversion

☐ Alteration (complete 2a & 10)

☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd

Material From To Amt sacks/lbs

Seal: Dia + From To Gauge Stl Plstc Wld Thrd

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic

☐ Irrigation

☐ Community

☐ Industrial/ Commercial

☐ Livestock

☐ Dewatering

☐ Thermal

☐ Injection

☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 341.00 ft.

BORE HOLE

Dia	From	To	Material	From	To	Amt	sacks/lbs
12	0	18	Bentonite	0	18	51	S
10.5	18	45			Calculated	6.2	
8	45	247	Cement	6	228	68	S
6	247	341			Calculated	19.61	

Seal placement method: ☐ A ☒ B ☐ C ☐ D ☐ E ☒ Other: BENTONITE POURED

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 6/29/2026 Begin Time 16 20

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+ From To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	8	☒ 1 45	0.250	ST	☒			45
C	6	☐ 6 228	0.250	ST	☒			228

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type Material

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrm/slot width	Slot length	# of slots	Tele/ Pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	30		277	1

Temperature 65 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 179 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County UMATILLA Twp 5.00 N N/S Range 28.00 E E/W WM

Sec 16 NE 1/4 of the NW 1/4 Tax Lot 601

Tax Map Number Lot

Lat ° ' " or 45.92183020 DMS or DD

Long ° ' " or -119.3222140 DMS or DD

☒ Street address of well ☐ Nearest address

82353 MUNGER LN, UMATILLA, OR 97882

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/7/2026			50

Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES

Depth water was first found 115.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
6/30/2026	115	222	5			49
7/7/2026	230	254	30			50

(11) WELL LOG

Ground Elevation 312.68 FT

Material	From	To
silty sand	0	1
sand	1	4
cemented gravels	4	8
clay/gravels	8	21
clay/gravels/cobbles	21	27
med black basalt	27	40
hard black basalt	40	115
fractured black basalt/blue clay	115	222
black basalt	222	230
frac black basalt	230	254
med black and grey frac basalt	254	261
med black and brown frac basalt	261	277
med black frac basalt	277	294
black and grey frac w/ blue streaks	294	302
black and brown frac basalt	302	317
soft black and red frac basalt w/blue streaks	317	331
med brown frac basalt	331	341

Construction

Begin Date 6/29/2026 Begin Time 12 18 End Date 7/7/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1766 Date 7/14/2026

Signed BRANDON BROWN (E-filed)

Drilling Company: Waterwell Developing & Surveys

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

(2a) PRE-ALTERATION

Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd

Material	From	To	Amt	sacks/lbs

(5) BORE HOLE CONSTRUCTION

BORE HOLE			SEAL			sacks/	
Dia	From	To	Material	From	To	Amt	lbs
			Cement	18	30	12	S
			Calculated				
			Calculated				
			Calculated				
			Calculated				

FILTER PACK			
From	To	Material	Size

(6) CASING/LINER

[illegible]

(7) PERFORATIONS/SCREENS

[illegible]

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)

Water Quality Concerns

[illegible]

(10) STATIC WATER LEVEL

[illegible]

(11) WELL LOG

[illegible]

Name of person(s) who assisted with construction and Trainee License # / Helper #

Assistant Name	Type	#
JUSTIN BOESCH	WATER	2060
HAIDEN DAY	HELPER WATER	8888942
ZANE ESTES	HELPER WATER	8889009
CLAYTON WRIGHT	HELPER WATER	8888969

Comments/Remarks

--

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

UMAT 59568

7/14/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.92183020 Datum: WGS84

Longitude: -119.32222140

Township/Range/Section/Quarter-Quarter Section:
WM5.00N28.00E16NENW

Address of Well:

82353 MUNGER LN, UMATILLA, OR 97882

Well Label: 157162

Printed: July 8, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

