

RECEIVED

5N/28E/25cb

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

JUN 13 1994

WATER RESOURCES DEPT.

(START CARD) # 46851

Instructions for completing this report are on the last page of this form. M. OREGON

(1) OWNER:

Name Poverty Acres, Inc. (Bryan Wolfe) Well Number 6037
Address Rt. 2, Box 2743
City Hermiston State OR Zip 97838

(2) TYPE OF WORK

[X] New Well [] Deepening [] Alteration (repair/recondition) [] Abandonment

(3) DRILL METHOD:

[X] Rotary Air [] Rotary Mud [] Cable [] Auger
[] Other

(4) PROPOSED USE:

[] Domestic [] Community [] Industrial [X] Irrigation
[] Thermal [] Injection [] Livestock [] Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval [] Yes [X] No Depth of Completed Well 38 ft.
Explosives used [] Yes [X] No Type Amount

Table with columns: HOLE Diameter, From, To, SEAL Material, From, To, Sacks or pounds. Row 1: 20", 0, 20, Bentonite, 0, 20, 23 sacks. Row 2: 16", 20, 38.

How was seal placed: Method [] A [] B [] C [] D [] E
[X] Other Poured 3/8" bentonite chips
Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Row 1: Casing 16", +1, 36, .375, [X], [], [X], [].

Final location of shoe(s) 36

(7) PERFORATIONS/SCREENS:

[X] Perforations Method Torch cut
[] Screens Type Material
From 30 To 36 Slot size 1/4" x 4" Number 10 rows Diameter 10 rows
Casing [X] Liner []

(8) WELL TESTS: Minimum testing time is 1 hour

Table with columns: Pump, Bailer, Air, Flowing Artesian, Yield gal/min, Drawdown, Drill stem at, Time. Row 1: 2,000, 38, 38, 1 hr.

Temperature of water 54.0 Depth Artesian Flow Found
Was a water analysis done? [] Yes By whom
Did any strata contain water not suitable for intended use? [] Too little
[] Salty [] Muddy [] Odor [] Colored [] Other
Depth of strata:

(9) LOCATION OF WELL by legal description:

County Umatilla Latitude Longitude
Township 5N N or S Range 28E E or W. WM.
Section 25 NW 1/4 SW 1/4
Tax Lot 4900 Lot Block Subdivision
Street Address of Well (or nearest address) East end of Klaus Lane, Hermiston, OR 97838

(10) STATIC WATER LEVEL:

15 ft. below land surface. Date 5-13-94
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 22

Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 22, 38, 2,000, 15.

(12) WELL LOG:

Table with columns: Material, From, To, SWL. Row 1: Sandy soil, 0, 1. Row 2: Sand, 1, 22. Row 3: Gravel, 22, 38, WB.

Date started 5-12-94 Completed 5-13-94

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed WWC Number Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Patrick Wallace WWC Number 1218 Date 5-31-94