

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy of this report  
are to be filed with the

**WATER WELL REPORT**

WATER RESOURCES DEPARTMENT,  
SALEM, OREGON 97310  
within 30 days from the date  
of well completion.

STATE OF OREGON  
(Please type or print)

*Unit 1063*

State Well No. 35/38E-13ab

State Permit No. \_\_\_\_\_

*Unit 1063*

(Do not write above this line)

**(1) OWNER:**

Name Walt Hansen  
Address Rt 2 Box 2705  
La Grande OR 97850

**(2) TYPE OF WORK (check):**

New Well  Deepening  Reconditioning  Abandon   
If abandonment, describe material and procedure in Item 12.

**(3) TYPE OF WELL:**

Rotary  Driven   
Cable  Jetted   
Dug  Bored

**(4) PROPOSED USE (check):**

Domestic  Industrial  Municipal   
Irrigation  Test Well  Other

**(5) CASING INSTALLED:**

Threaded  Welded   
10" Diam. from 1 ft. to 150 ft. Gage 279  
" Diam. from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Gage \_\_\_\_\_  
" Diam. from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Gage \_\_\_\_\_

**(6) PERFORATIONS:**

Perforated?  Yes  No.  
Type of perforator used factory  
Size of perforations 1/8 in. by 3 in.  
670 perforations from 90 ft. to 150 ft.  
perforations from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
perforations from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

**(7) SCREENS:**

Well screen installed?  Yes  No  
Manufacturer's Name \_\_\_\_\_  
Type \_\_\_\_\_ Model No. \_\_\_\_\_  
Diam. \_\_\_\_\_ Slot size \_\_\_\_\_ Set from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
Diam. \_\_\_\_\_ Slot size \_\_\_\_\_ Set from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

**(8) WELL TESTS:**

Drawdown is amount water level is lowered below static level  
Was a pump test made?  Yes  No If yes, by whom?  
Yield: gal./min. with \_\_\_\_\_ ft. drawdown after \_\_\_\_\_ hrs.  
" " " " " "  
" " " " " "  
Bailer test 100 gal./min. with 20 ft. drawdown after 1 hrs.  
Artesian flow \_\_\_\_\_ g.p.m.  
Temperature of water \_\_\_\_\_ Depth artesian flow encountered \_\_\_\_\_ ft.

**(9) CONSTRUCTION:**

Well seal—Material used Portland Cement  
Well sealed from land surface to 19 ft.  
Diameter of well bore to bottom of seal 17 in.  
Diameter of well bore below seal 17 in.  
Number of sacks of cement used in well seal 25 sacks  
How was cement grout placed? pumped  
Was a drive shoe used?  Yes  No Plugs \_\_\_\_\_ Size: location \_\_\_\_\_ ft.  
Did any strata contain unusable water?  Yes  No  
Type of water? \_\_\_\_\_ depth of strata \_\_\_\_\_  
Method of sealing strata off \_\_\_\_\_  
Was well gravel packed?  Yes  No Size of gravel: 3/4  
Gravel placed from 20 ft. to 150 ft.

**(10) LOCATION OF WELL:**

County Union Driller's well number 79-2  
NW 1/4 NE 1/4 Section 13 T. 35 R. 38E W.M.  
Bearing and distance from section or subdivision corner  
1300 ft. W. & 60 ft. South of NE CORNER  
of Sec 13 T. 35 R. 38E W.M.

**(11) WATER LEVEL: Completed well.**

Depth at which water was first found 25 ft.  
Static level 9 ft. below land surface. Date 7-25-79  
Artesian pressure \_\_\_\_\_ lbs. per square inch. Date \_\_\_\_\_

**(12) WELL LOG:**

Diameter of well below casing none  
Depth drilled 150 ft. Depth of completed well 150 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
soil blacke brown	0	5	
sand fine	5	10	
clay & sand sth	10	20	
sand med	20	25	
gravel med	25	40	
Basalt brown	40	50	
gravel med	50	82	
clay gr.	82	86	
gravel med w/ clay sth.	86	150	

Work started 7-17 19 79 Completed 7-25 19 79  
Date well drilling machine moved off of well 7-25 19 79

**Drilling Machine Operator's Certification:**

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.  
[Signed] Ernest J. Staal Date 8-5, 1979  
(Drilling Machine Operator)  
Drilling Machine Operator's License No. 698

**Water Well Contractor's Certification:**

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.  
Name Court Right IRR Ser.  
(Person, firm or corporation) (Type or print)  
Address Rt. 1 Box 1685 La Grande OR  
[Signed] Ernest J. Staal  
(Water Well Contractor)  
Contractor's License No. 206 Date 8-5, 1979