

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON
within 30 days from the date of well completion.

WATER WELL REPORT STATE OF OREGON STATE ENGINEER SALEM, OREGON

State Well No.

State Permit No.

(1) OWNER:

Name ART Mc CALL
Address RT. 2 LAGRANDE, ORE 97850

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 300 ft. Gage 25
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(5) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used

Size of perforations in. by in.
1600 perforations from 50 ft. to 100 ft.
3200 perforations from 110 ft. to 300 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 5 ft. below land surface Date 8/15/70
Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " "

Bailer test 150 gal./min. with 10 ft. drawdown after 1 hrs.
Artesian flow g.p.m. Date

Temperature of water 58° Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used cement
Depth of seal 30 ft.
Diameter of well bore to bottom of seal 24 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☐ Yes ☒ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/8"
Gravel placed from 30 ft. to 30 ft.

(11) LOCATION OF WELL:

County Driller's well number
1/4 1/4 Section 32 T. 35 R. 38 E W.M.

Bearing and distance from section or subdivision corner

Approx 1500' W. & 1300' S. of NE corner of above

(12) WELL LOG:

Diameter of well below casing 9 7/8"

Depth drilled 329 ft. Depth of completed well 300 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top soil & brown clay	0	8	
Blue clay	8	16	
Gravel, boulders & clay	16	39	
Small gravel & clay	39	55	
Small boulders, gravel & fine clay	55	85	
Medium sand to boulders	85	130	
Brown sandy clay, fine gravel/streaks	130	170	
Blue clay, gravel/streaks	170	205	
Coarse sand, few clay streaks	205	329	

Work started 7/22 1970 Completed 8/15 1970

Date well drilling machine moved off of well 8/15 1970

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] J. Plonville Date 8/30, 1970
(Drilling Machine Operator)

Drilling Machine Operator's License No. 388

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME CARRIE & SARGWICK, INC.
(Person, firm or corporation) (Type or print)

Address Box 613 LAGRANDE, ORE

[Signed] J. Plonville
(Water Well Contractor)

Contractor's License No. 517 Date 8/30, 1970