

**WATER RESOURCES DEPARTMENT.
SALEM, OREGON 97310**
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

(Do not write above this line)

State Well No. 551402-100

State Permit No. _____

(1) OWNER:

Name CHUCK PHINNEY
Address RT 1 BOX 74 COVE. OKA. 97824

(2) TYPE OF WORK (check):

New Well ☒ **Deepening** ☐ **Reconditioning** ☐ **Abandon** ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary	☐	Driven	☐
Cable	☒	Jetted	☐
Γ	☐	Bored	☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

5) CASING INSTALLED:

5) CASING INSTALLED: Threaded ☐ Welded ☒
 6" Diam. from 0 ft. to 151 ft. Gage 250
 " Diam. from ft. to ft. Gage
 " Diam. from ft. to ft. Gage

2) PERFORATIONS:

*) **PERFORATIONS:** Perforated? ☒ Yes ☐ No.

Type of perforator used TORCH

Size of perforations 1/4 in. by 6 in.

6.2 perforations from 121 ft. to 149 ft.

perforations from _____ ft. to _____ ft.

perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
 Type Model No.
 Diam. Slot size Set from ft. to ft.
 Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

1:	gal./min. with	ft. drawdown after	hrs.
"	"	"	"
"	"	"	"

Bailer test 18 gal./min. with 80 ft. drawdown after 1 1/2 hrs.

/ dian flow g.p.m.

(9) CONSTRUCTION:

Well seal—Material used CEMENT
Well sealed from land surface to 22 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 11 sacks
How was cement grout placed? PUMPED THROUGH PIPE IN 10 in. HOLE

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County UNION Driller's well number 161
NE ¼ SE ¼ Section 10 T. 3 S. R. 40 E. W.M.

Bearing and distance from section or subdivision corner
Approx. 1420 FT. NORTH AND 1370 FT. WEST
OF THE SOUTHEAST CORNER OF SECTION 10

(11) WATER LEVEL: Completed well.

Depth at which water was first found 33 ft.

Static level 12 ft. below land surface. Date 10-4-79

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

(12) WELL LOG: Diameter of well below casing 6 in.
Depth drilled 167 ft. Depth of completed well 167 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

[illegible]

Work started Sept. 13 19 79 Completed Oct. 4 19 79
Date well drilling machine moved off of well Oct. 5 19 79

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Ronald A. Moore Date Oct. 8, 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 9/3**Water Well Contractor's Certification:**

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name MOORE WELL DRILLING
(Person, firm or corporation) (Type or print)

Address RT 1 Box 1 Cove, Ore. 97824

[Signed] Ronald G. Moore
(Water Well Contractor)

Contractor's License No. 655 Date Oct. 8 1979