

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 33/40E-15 ad

State Permit No. _____

(1) OWNER:

Name CHUCK PHINNEY

Address RT 1 BOX 74
COVE, ORE. 97824

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cased ☒ Jetted ☐
Lined ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 120 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used TORCH

Size of perforations 5/32 in. by 7 in.
54 perforations from 90 ft. to 117 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " "
" " " "

Pump test 8 gal./min. with 110 ft. drawdown after 1 hrs.

Artesian flow 1/3 g.p.m.

Temperature of water 51° Depth artesian flow encountered 76 ft.

(9) CONSTRUCTION:

Well seal—Material used PORTLAND CEMENT
Well sealed from land surface to 21 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 15 sacks
How was cement grout placed?
PUMPED THROUGH PIPE IN 10 IN. HOLE.

Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County UNION Driller's well number _____
SE 1/4 NE 1/4 Section 15 T. 35S. R. 40E. W.M.

Bearing and distance from section or subdivision corner

APPROX. 1670 FT. SOUTH AND 568 FT. WEST
OF THE NORTHEAST CORNER OF SECTION 15

(11) WATER LEVEL: Completed well.

Depth at which water was first found 76 ft.

Static level 0 ft. below land surface. Date 10-7-80

Artesian pressure LESS THAN 1 lbs. per square inch. Date 10-20-80

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 125 ft. Depth of completed well 125 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	3	
CLAY, BR. GRAVEL, LG.	3	23	
CLAY, BR. BOULDER, MED.	23	68	
CLAY, BR.	68	70	
CLAY, BR. GRAVEL, MED.	70	76	
GRAVEL, SM. (W)	76	77	0
CLAY, BR. GRAVEL, LG.	77	86	
CLAY, BR.	86	101	
CLAY, BR. GRAVEL, MED.	101	116	
GRAVEL, SM. (W)	116	117	0
CLAY, BR. GRAVEL, LG.	117	125	0

RECEIVED

OCT 22 1980

WATER RESOURCES DEPT
SALEM, OREGON

Work started SEPT. 24 1980 Completed OCT. 6 1980

Date well drilling machine moved off of well OCT. 7 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Ronald G. Moore Date OCT. 20, 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 913

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name MOORE WELL DRILLING
(Person, firm or corporation) (Type or print)

Address RT 1 BOX 1 COVE, ORE. 97824

[Signed] Ronald G. Moore
(Water Well Contractor)

Contractor's License No. 655 Date OCT. 20, 1980