

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED

JUL 25 1986

PLEASE TYPE or PRINT IN INK

WATER RESOURCES DEPT

(for official use only)

(1) OWNER:

Name JERRY HUDSON
Address Box 360
City SUMMERVILLE State OR

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐
Rotary Mud ☐ Dug ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Thermal: ☐ Withdrawal ☐ Reinjection ☐
Other: ☐ Piezometric ☐ Grounding ☐ Test ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☒ Welded ☐
6" Diam. from 12 ft. to 38 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

Steel ☐ Plastic ☒
Threaded ☐ Welded ☒
4" Diam. from 25 ft. to 140 ft. Gauge 50R-21

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Size of perforations 45/64 in. by 6 in.
perforations from 100 ft. to 140 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☐ Yes ☒ No If yes, by whom?
Id: gal./min. with ft. drawdown after hrs.
Air test 12 gal./min. with drill stem at 135 ft. 1 hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water 55.0 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒
Well seal—Material used CEMENT
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Amount of sealing material PUMP 14 sacks ☒ pounds ☐
How was cement grout placed?
Was pump installed? Type HP Depth ft.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from ft. to ft.

(10) LOCATION OF WELL by legal description:

County UNION SE 1/4 NE 1/4 of Section 8 of Township 15 Range 38E WM.
(Township is North or South) (Range is East or West)

Tax Lot Lot Block Subdivision

MAILING ADDRESS OF WELL (or nearest address)

(11) WATER LEVEL of COMPLETED WELL:

Depth at which water was first found 125 ft.
Static level 23 ft. below land surface. Date 6/12/86
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 0
Depth drilled 140 ft. Depth of completed well 140 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	2	
BROWN CLAY & COARSE GRAVEL	2	38	
BROWN CLAY	38	62	
FINE TO MEDIUM GRAVEL WITH SOME BROWN CLAY	62	86	
BROWN CLAY	86	96	
MEDIUM TO FINE GRAVEL	96	103	
BROWN CLAY	103	108	
FINE TO MEDIUM GRAVEL	108	140	23'

Date work started 6/10/86 completed 6/12/86
Date well drilling machine moved off of well 6/13 1986

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] James Berry Date 6/13, 1986

(bonded) Water Well Constructor Certification:

Bond 280-216-78 Issued by: WESTERN SURETY
(number) (Surety Company Name)

On behalf of JAMES BERRY
(type or print name of Water Well Constructor)

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief:

(Signed) James Berry (Water Well Constructor)

(Date) 6/13/86

NOTICE TO WATER WELL CONSTRUCTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*46866-690