

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date of well completion.

RECEIVED
JUL 26 1967
STATE OF OREGON
(Please type or print)
DATE ABOVE THIS LINE
STATE ENGINEER
SALEM, OREGON

State Well No. 1/39-5 H

State Permit No. 179

(1) OWNER:

Name Russell Hug
Address Summerville Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(11) LOCATION OF WELL:

County UNION Driller's well number 771
SE 1/4 NE 1/4 Section 5 T. 1S R. 39E W.M.
Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 10

Depth drilled 402 ft. Depth of completed well 400 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top Soil (Light)	1	4	
GRAVEL SMALL	4	8	
BASALT grey (VERY HARD)	8	93	
" " (FRACTURED)	93	97	
" " VERY HARD	97	104	
" " FRACTURED	104	107	
" " VERY HARD	107	148	
CLAY grey light	148	165	
BASALT Black broken	165	180	
BASALT " " w. clay	180	245	
CLAY grey light	245	260	
BASALT Black broken	245	260	
CLAY grey light	260	283	
CLAY " " SANDY	283	320	
" " WITH ROD	320	345	
BASALT Black broken w. gravel	345	384	
" Red CINDERS	384	395	
BASALT Black broken	395	402	

Work started 5/1/ 1967 Completed 6/23/ 1967

Date well drilling machine moved off of well 6/27 1967

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Sam M. M. M. Date July 18 1967
(Drilling Machine Operator)

Drilling Machine Operator's License No. 283

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME INTERVALLEY DRILLING CO.
(Person, firm or corporation) (Type or print)

Address P.O. Box 471 Island City, Oregon

[Signed] W. E. Ellsworth
(Water Well Contractor)

Contractor's License No. 328 Date 7/18, 1967