

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 10/38E-156b

State Permit No.

(1) OWNER:

Name Paul Lively
Address P.O. Box 29 Summerville, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 1 ft. to 6.9 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.
Type of perforator used Torch

Size of perforations 1/4 in. by 6 in.
20 perforations from 19 ft. to 49 ft.
10 perforations from 30 ft. to 40 ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " " " "

Bailer test 8 gal./min. with 38 ft. drawdown after 1 hrs.
Artesian flow g.p.m.

Temperature of water 50 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used cement
Well sealed from land surface to 21 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 11 sacks
How was cement grout placed? grout pump

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Union Driller's well number
HW 1/4 NW 1/4 Section 15 T. 15 R. 38E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 24 ft.
Static level 18 ft. below land surface. Date
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6
Depth drilled 80 ft. Depth of completed well 76 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Rocky Soil	0	5	
CLAY BROWN	5	16	
GRAVELLY CLAY	16	24	
SMALL GRAVEL	24	25	
LITTLE WATER			
GRAVEL COARSE	25	51	
CLAY BROWN			
GRAVELLY CLAY	51	63	
GRAVEL med.	63	66	
WATER BEARING			
GRAVELLY CLAY	66	80	

RECEIVED

JUL 27 1979

WATER RESOURCES DEPT
SALEM, OREGON

Work started June 26 1979 Completed June 29 1979
Date well drilling machine moved off of well June 29 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] O.C. Tandy Date June 30 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 6

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name O.C. Tandy
(Person, firm or corporation) (Type or print)

Address 14034 Ave. La Grande, Oregon

[Signed] O.C. Tandy
(Water Well Contractor)

Contractor's License No. 29 Date June 30 1979