

WATER RESOURCES DEPARTMENT.
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

(Do not write above this line)

State Well No. 25/38E-14 CC
State Permit No. _____

(1) OWNER:

Name DORIS VAN BLOKLAND
Address RT 1 BOX 1664 E. LA GRANDE, ORE 97850

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 85 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.
Type of perforator used TORCH
Size of perforations 1/8 in. by 7 in.
53 perforations from 6.5 ft. to 8.3 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☐ Yes ☒ No If yes, by whom?
d: _____ gal./min. with _____ ft. drawdown after _____ hrs.
" " " "
" " " "
Bailer test 24 gal./min. with 47 ft. drawdown after 1 1/2 hrs.
Artesian flow _____ g.p.m.
Temperature of water 52 Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used PORTLAND CEMENT
Well sealed from land surface to 22 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 13 sacks
How was cement grout placed?
PUMPED THROUGH PIPE IN 10 IN. HOLE.
Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County UNION Driller's well number _____
SW 1/4 SW 1/4 Section 14 T. 2 S. R. 38 E. W.M.
Bearing and distance from section or subdivision corner

APPROX. 650 FT. EAST AND 1285 FT. NORTH OF THE SOUTHWEST CORNER OF SECTION 14

(11) WATER LEVEL: Completed well.

Depth at which water was first found 53 ft.
Static level 13 ft. below land surface. Date 9-5-80
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6
Depth drilled 86 ft. Depth of completed well 86 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	4	
CLAY, BR.	4	45	
CEMENTED GRAVEL	45	53	
GRAVEL, MED. SAND, MED. (W)	53	61	13
CLAY, BR.	61	78	
GRAVEL, MED. (W)	78	81	13
CLAY, GRAY	81	86	13

RECEIVED

SEP 15 1980

WATER RESOURCES DEPT
SALEM, OREGON

Work started AUG. 28 1980 Completed SEPT. 5 1980
Date well drilling machine moved off of well SEPT. 5 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Ronald A. Moore Date SEPT. 8, 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 913

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name MOORE WELL DRILLING
(Person, firm or corporation) (Type or print)

Address RT 1 BOX 1 COVE, ORE 97824

[Signed] Ronald A. Moore
(Water Well Contractor)

Contractor's License No. 655 Date SEPT. 8, 1980