

RECEIVED

UNIO
50504

JUN 4 1999

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPT.
SALEM, OREGON

WELL I.D. # L. 07100
START CARD # 1R1616

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number _____
Name LA Grande Polo Club LTD
Address PO Box 3230
City LA Grande State OR Zip 97250

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 260 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE				SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds	
12	0	22	Cement	10	22	5 SACKS	
8	22	265	Bentonite	0	10	8 SACKS	

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other Poured Bentonite
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to NO G Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 8	12	257	260	☒	☐	☒	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s) 257 (8")

(7) PERFORATIONS/SCREENS:

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
80	120	4x2	200	8"		☒	☐
180	200	4x2	100	8"		☒	☐
220	240	4x2	100	8"		☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailer ☒ Air ☐ Flowing
Yield gal/min 200 Drawdown _____ Drill stem at _____ Time 3 hr.
Temperature of water 58 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Union Latitude _____ Longitude _____
Township 35 N or S Range 88E E or W. WM.
Section 26 NW 1/4 NE 1/4
Tax Lot 8105 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) Union LA Grande Hwy Next to R 25 Yard

(10) STATIC WATER LEVEL:
8 ft. below land surface. Date 5-28-99
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 90

From	To	Estimated Flow Rate	SWL
90	100	200	8'
105	115	100	8'
155	200	100	8'
220	240	300	8'

(12) WELL LOG:
Ground Elevation _____

Material	From	To	SWL
Brown sandy clay	0	19	
Grey clay	19	36	
Brown sandy clay w/ gravel	36	135	
Dirty sand	135	143	8'
Blue sandy clay	143	195	8'
Blue clay & gravel	195	200	8'
Blue clay	200	255	8'
Brown sandy clay w/ g	255	265	8'

Date started 5-25-99 Completed 5-28-99

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
Signed _____ WWC Number _____ Date _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed Ralph W. Stiffel WWC Number 415 Date 5-31-99