

STATE OF OREGON
 WATER SUPPLY WELL REPORT
 (as required by ORS 537.765)

WELL I.D. # L 81756

START CARD # 181957

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number _____
 Name Eagles Hot Lake RU Park
 Address PO BOX 773 65182 HOT LAKE LANE
 City LA Grande State OR Zip 97850

(2) TYPE OF WORK New Well
 Deepening Alteration (repair/recondition) Abandonment Conversion

(3) DRILL METHOD
 Rotary Air Rotary Mud Cable Auger Cable Mud
 Other _____

(4) PROPOSED USE
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other _____

(5) BORE HOLE CONSTRUCTION Special Construction: Yes No
 Depth of Completed Well 565 ft.
 Explosives used: Yes No Type _____ Amount _____

BORE HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or Pounds
12	0	100	Cement	32	100	32 SACKS
			Bentonite	0	32	26 SACKS
8	100	525				

How was seal placed: Method A B C D E

Other Poured Bentonite

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to NONE Size of gravel _____

(6) CASING/LINER

Casing:	Diameter	From	To	Gauge	Material			
					Steel	Plastic	Welded	Threaded
	8"	+3	457	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:			<u>NONE</u>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Drive Shoe used Inside Outside None
 Final location of shoe(s) 8" 457'

(7) PERFORATIONS/SCREENS
 Perforations Method _____
 Screens Type _____ Material _____

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
			<u>NONE</u>			<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailer Air Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
<u>40+</u>		<u>420</u>	

Temperature of water 78° Depth Artesian Flow Found _____

Was a water analysis done? Yes By whom _____

Did any strata contain water not suitable for intended use? Too little

Salty Muddy Odor Colored Other _____

Depth of strata: _____

(9) LOCATION OF WELL (legal description)
 County Union
 Tax Lot 800 Lot _____
 Township 42 N or S Range 29E E or W WM
 Section 5 NE 1/4 SW 1/4

Lat _____ ° _____ ' _____ " or _____ (degrees or decimal)
 Long _____ ° _____ ' _____ " or _____ (degrees or decimal)

Street Address of Well (or nearest address) 65182 HOT LAKE (R.V. PARK) LA Grande OR LANE

(10) STATIC WATER LEVEL
3' ft. below land surface. Date 12-2-05
 _____ ft. below land surface. Date _____
 Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES

Depth at which water was first found 480

From	To	Estimated Flow Rate	SWL
480	490	10	3
545	565	40+	3

(12) WELL LOG Ground Elevation _____

Material	From	To	SWL
TOP SOIL	0	3	
Gray Clay	3	24	
Gray Clay Broken Rock	24	26	
Gray Clay	26	195	
Brown Clay Rock	195	230	
Gray Basalt	230	410	
Gray Clay & Gravel	410	450	
Gray Shale & Gravel	450	525	
Brown Clay & Gravel	525	565	3

DEC 15 2005

Date Started 11-30-05 Completed 12-6-05

(unbonded) Water Well Constructor Certification
 I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number 1640 Date 11-30-05

Signed [Signature]

(bonded) Water Well Constructor Certification
 I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 415 Date 12-13-05

Signed [Signature]