

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 85257
START CARD # 172239

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER C.C.P.D. INC Well Number _____
Name P.O. Box 203
Address PENDLETON State OR Zip 97801

(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☒ Other REVERSE

(4) PROPOSED USE
☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well 280 ft.
Explosives used: ☐ Yes ☒ No Type _____ Amount _____

BORE HOLE				SEAL			
Diameter	From	To	Material	From	To	Sacks or Pounds	
28	0	300	BENTONITE	0	32	7500	

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other DRY POUR
Backfill placed from N/A ft. to _____ ft. Material _____
Gravel placed from 32 ft. to 300 ft. Size of gravel 3/8

(6) CASING/LINER

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 18	+2	110	.375	☒	☐	☒	☐
18	200	220	.375	☒	☐	☒	☐
18	250	280	.375	☒	☐	☒	☐
Liner:				☐	☐	☐	☐

Drive Shoe used ☐ Inside ☐ Outside ☒ None
Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS
☐ Perforations Method _____
☒ Screens Type WIRE WRAP Material M.S.

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
110	200	.035		18		☒	☐
220	250	.035		18		☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailor ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
250 gpm	70'	200	2 hrs

Temperature of water 62 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Yes ☐ No

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata: _____

(9) LOCATION OF WELL (legal description)

County UNION
Tax Lot 10200 Lot _____
Township 2 N or S Range 39 E or W WM
Section 25 SW 1/4 SW 1/4

Lat _____ " or _____ (degrees or decimal)
Long _____ " or _____ (degrees or decimal)

Street Address of Well (or nearest address) CARLE AD SOUTH OF BOOTH LANE APP. 1/2 MILE

(10) STATIC WATER LEVEL
18 ft. below land surface. Date 2-16-07
_____ ft. below land surface. Date _____
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES

Depth at which water was first found 31'

From	To	Estimated Flow Rate	SWL
<u>ALL SANDS + GRAVELS BELOW 31'</u>			

(12) WELL LOG

Material	From	To	SWL
TOP SOIL	0	7	
CLAY	7	31	
FINE SAND	31	40	
BROWN CLAY SAND LAYER	40	50	
FINE SAND, SOME CLAY	50	77	
CLAY W/SM SAND LAYER	77	113	
FINE-MED SAND GRAVEL	113	133	
BL SHALE SAND STONE	133	140	
BLUE CLAY	140	143	
SAND GRAVEL	143	147	
BLUE CLAY SAND LAYER	147	172	
FINE SAND	172	202	
BLUE CLAY SHALE	202	220	
FINE SAND	220	251	
BLUE CLAY	251	300	

Date Started 1-17-07 Completed 2-16-07

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number 1673 Date 3-14-07

Signed Kevin Chute

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1505 Date 3-14-07

Signed Steve D. [Signature]

RECEIVED

MAR 19 2007