

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 91038START CARD # 193902

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number _____
Name Kim & Gloria Bowman
Address 64504 Aspen Rd
City La Grande State OR Zip 97850

(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Other _____

(4) PROPOSED USE
☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well 645 ft.
Explosives used: ☐ Yes ☒ No Type _____ Amount _____

BORE HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or Pounds
12	0	60	Cement	40	65	105 sacks
8	60	645	Portland	0	40	Portland 340 sacks

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E

☐ Other Pour
Backfill placed from 55 ft. to 60 ft. Material sand
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 8	72	631	.250	☒	☐	☐	☐
Liner:		<u>NONE</u>		☐	☐	☐	☐

Drive Shoe used ☐ Inside ☒ Outside ☐ None
Final location of shoe(s) 8" 631

(7) PERFORATIONS/SCREENS
☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
			<u>NONE</u>			☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
<u>100+</u>		<u>600</u>	<u>2 hrs</u>

Temperature of water 54° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL (legal description)

County Union
Tax Lot 100 Lot _____
Township 25 N or S Range 38E E or W WM
Section 17 NE 1/4 NE 1/4

Lat _____ " or _____ (degrees or decimal)
Long _____ " or _____ (degrees or decimal)

Street Address of Well (or nearest address) 64504 Aspen Rd
La Grande OR 97850

(10) STATIC WATER LEVEL
76 ft. below land surface. Date 7-12-07

_____ ft. below land surface. Date _____
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES
Depth at which water was first found 620

From	To	Estimated Flow Rate	SWL
<u>620</u>	<u>645</u>	<u>100+</u>	<u>76</u>

(12) WELL LOG Ground Elevation _____

Material	From	To	SWL
Top Soil	0	5	
Brown Clay & Gravel	5	33	
Brown Clay (Hard)	33	55	
Brown Clay & Gravel	55	70	
Gray Clay	70	155	
Gray Clay & Gravel	155	380	
Gray Clay	380	468	
Tan Clay & Gravel	468	620	
Fractured Black Basalt	620	645	76'

Date Started 7-2-07 Completed 7-12-07

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number 1737 Date 7-31-07

Signed Michael J. [Signature]

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 415 Date 7-31-07

Signed Robert V. [Signature]

RECEIVED