

STATE OF OREGON
WATER SUPPLY WELL REPORT

UNIO 53127

WELL I.D. LABEL# L

161103

START CARD #

1083464

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

9/16/2026

(1) LAND OWNER

Owner Well I.D. _____

First Name ANDYLast Name ZETTLE

Company _____

Address 75012 YARRINGTON RDCity ELGINState ORZip 97827**(2) TYPE OF WORK**☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing:

Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd
					☐	☐	☐	☐

Seal:

Material	From	To	Amt	sacks/lbs

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other _____
(4) PROPOSED USE
☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other _____
(5) BORE HOLE CONSTRUCTIONSpecial Standard ☐ (Attach copy)Depth of Completed Well 266.00 ft.

BORE HOLE				SEAL				sacks/
Dia	From	To	Material	From	To	Amt		lbs
12	0	18	Bentonite Chips	0	18	18	S	
8	18	266			Calculated	10.21		
					Calculated			

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POURED BENTONITE

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____Seal Placement Begin Date 9/10/2026 Begin Time 13 00**(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	8	☒	2	18	0.250	ST	☒			
L	4.5		6	246	Sch40	PL		☒		

Temp casing ☐ Yes Dia _____ From + ☐ _____ To _____**(7) PERFORATIONS/SCREENS**

Perforations Method _____

Screens Type FACTORY SLOTTED Material SCH-40

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
Screen	Liner	4.5	246	266	.013	1		Telescope

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	0.3		266	1

Temperature 67 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 131 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)County UNIO Twp 2.00 N N/S Range 40.00 E E/W WMSec 4 NW 1/4 of the SE 1/4 Tax Lot 200

Tax Map Number _____ Lot _____

Lat _____ ° _____ ' _____ " or 45.68122632 DMS or DD

Long _____ ° _____ ' _____ " or -117.81363632 DMS or DD

☒ Street address of well ☐ Nearest address75012 YARRINGTON RD, ELGIN, OR 97827**(10) STATIC WATER LEVEL**

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	9/14/2026			182
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 182.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
9/14/2026	182	217	0.3			182

(11) WELL LOGGround Elevation 3391.33 FT

Material	From	To
SOIL	0	2
BLACK BASALT	2	69
BLACK BROWN BASALT / TAN CLAYSTONE	69	84
BLACK BASALT	84	101
BLACK BROWN BASALT	101	145
BLACK BROWN BASALT / TAN CLAYSTONE	145	151
TAN CLAYSTONE	151	182
BLACK BROWN BASALT / TAN CLAYSTONE	182	217
BLACK BASALT	217	266

Construction

Begin Date 9/10/2026 Begin Time 07 29 End Date 9/14/2026**(unbonded) Water Well Constructor Certification**

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2061 Date 9/15/2026Signed KEYANO WALKER (E-filed)**(bonded) Water Well Constructor Certification**

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1735 Date 9/15/2026Signed CHAD COURTNEY (E-filed)Drilling Company: COURTNEY WELL DRILLING

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

UNIO 53127

9/16/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.68122632 Datum: WGS84

Longitude: -117.81363632

Township/Range/Section/Quarter-Quarter Section:
WM2.00N40.00E4NWSE

Address of Well:

75012 YARRINGTON RD, ELGIN, OR 97827

Well Label: 161103

Printed: September 16, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

