

NOTICE TO WATER WELL CONTRACTOR
The original first copy
of this report is to be
filed with the
STATE ENGINEER, SALEM, OREGON
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)
(Do not write above this line)

State Well No. 2/39-34 aca

State Permit No. _____

(1) OWNER:

Name Bob Gulzow
Address RT. 2 LAGRANDE, ORE.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

1 1/2" Diam. from 0 ft. to 178 ft. Gage 25
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used EXCAVATOR
Size of perforations 3/8 in. by 3 in.
1280 ft. perforations from 28 ft. to 98 ft.
3200 ft. perforations from 98 ft. to 178 ft.
_____ ft. perforations from _____ ft. to _____ ft.
_____ ft. perforations from _____ ft. to _____ ft.
_____ ft. perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WATER LEVEL: Completed well.

Static level 6 1/2 ft. below land surface Date 4/1/71
Artesian pressure _____ lbs. per square inch Date _____

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? COURTNEY IRRIGATION
Yield: 1200 gal./min. with 120 ft. drawdown after 24 hrs.

Ball test _____ gal./min. with _____ ft. drawdown after _____ hrs.
Artesian flow _____ g.p.m. Date _____

Temperature of water 50 Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used cement
Depth of seal 20 ft.
Diameter of well bore to bottom of seal 24 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☐ Yes ☒ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☒ Yes ☐ No Size of gravel: 1/4
Gravel placed from 20 ft. to 178 ft.

(11) LOCATION OF WELL:

County UNION Driller's well number _____
1/4 1/4 Section 34 T. 2 S. R. 39 E. W.M.

Bearing and distance from section or subdivision corner

Approx 1520' W. & 1330' S of N.E. corner of above

(12) WELL LOG:

Diameter of well below casing 12"

Depth drilled 280 ft. Depth of completed well 178 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Topsoil	0	1	
Brown Sand	1	8	
Brown Sandy clay	8	61	
Coarse sand, fine gravel	61	75	
" " some clay	75	81	
" " gravel	81	95	
Brown clay	95	103	
Coarse gravel	103	131	
Blue clay	131	135	
Fine gravel, coarse sand	135	153	
" " " "			
w/ clay sticks	153	180	
Blue sandy clay	180	280	

Work started 2/1 19 71 Completed 4/1 19 71
Date well drilling machine moved off of well 4/1/71 19 71

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] J. P. Corvill Date 4/30, 19.71.
(Drilling Machine Operator)

Drilling Machine Operator's License No. 388

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME CARRIE E. EDGEMAN, INC.
(Person, firm or corporation) (Type or print)

Address Box 443 LAGRANDE, ORE. 97853

[Signed] J. P. Corvill
(Water Well Contractor)

Contractor's License No. 517 Date 4/30, 19.71.