

STATE OF OREGON
WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

WELL I.D. # L 41 867

START CARD # 133763

(1) LAND OWNER Greg Blacklock Well Number _____
Name Greg Blacklock
Address 6606 Hurricane Creek Rd
City Joseph State OR Zip 97846

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:
☐ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☐ No Depth of Completed Well 520 ft.
Explosives used ☒ Yes ☐ No Type TR2 Amount 11 362 lb

HOLE			SEAL			Sacks or pounds
Diameter	From	To	Material	From	To	
10	0	25	Concrete	10	25	10 sacks
			Bentonite	0	10	6 sacks

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other Painted Bentonite

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6	12	131	.250	☒	☐	☒	☐
	5	1	156	.250	☒	☐	☒	☐
Liner:					☐	☐	☐	☐

Drive Shoe used ☐ Inside ☐ Outside ☐ None
Final location of shoe(s) 5" 156 6" 134

(7) PERFORATIONS/SCREENS:
☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

	Pump	Bailer	Air	Flowing
	Yield gal/min	Drawdown	Drill stem at	Time
	7"		480	1 hr.

Temperature of water 47° Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Walla Walla Latitude _____ Longitude _____
Township 25 N or S Range 44E E or W. WM.
Section 35 NE 1/4 SW 1/4
Tax Lot 1603 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 6606 Hurricane Creek Rd Joseph OR

(10) STATIC WATER LEVEL:
130 ft. below land surface. Date 9-14-00
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 440

From	To	Estimated Flow Rate	SWL
440	490	7"	

(12) WELL LOG:
Ground Elevation _____

Material	From	To	SWL
Top Soil	0	6	
Boulders & Clay	6	65	
Brown Clay & Gravel	65	90	
Large Boulders Clay	90	190	
Sand & Gravel w/ Boulders	190	565-440	
Steel RT 159' appears to			
Be part of one of the Drive			
shaes. Encountered extreme			
CAVING conditions between			
150 to over 200			

RECEIVED
OCT 20 2000
WATER RESOURCES DEPT.
SALEM, OREGON

Date started 8-30-00 Completed 9-14-00
(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
Signed Michael J. J. J. WWC Number 1737 Date 10-11-00

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed Robert V. J. J. WWC Number 574 Date 10-11-00