

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

WALL
771

RECEIVED

JUL 25 1994

(START CARD) # 64842

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Name Gircho F Cattle Co Inc
Address 68865 ELK MT RD
City Enterprise State OR Zip 97828

Well Number

SALEM, OREGON

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 196 ft.
Explosives used ☒ Yes ☐ No Type TR2 Amount 3 sticks

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
16	0	24	Cement Grout	0	24	26 sacks
12	24	196				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	12	1	146	220	☒	☐	☒	☐
	10	136	196	240	☐	☐	☐	☐
Liner:					☐	☐	☐	☐

Final location of shoe(s) 12" 146 10" 196

(7) PERFORATIONS/SCREENS:

☐ Perforations Method Touch
☐ Screens Type _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
50	146	4x4	2000			☒	☐
140	196	4x4	600			☒	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☐ Air ☐ Flowing
Yield gal/min Drawdown Drill stem at Time
200 160 _____ 1 hr.

Temperature of water 57.0 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Wallowa Latitude _____ Longitude _____
Township 1S N or S Range 45E E or W. WM.
Section 4 SE 1/4 SW 1/4
Tax Lot 2200 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 68865 ELK MT RD
Enterprise OR

(10) STATIC WATER LEVEL:

7' ft. below land surface. Date 7-20-94
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 85

From	To	Estimated Flow Rate	SWL
65	85	60	7
116	128	140	7

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Top Soil	0	3	
Soft Brown Clay Gravel	3	85	
Cemented Gravel	85	116	7'
Red Clay & Rock	116	128	7
Brown Clay & Rock	128	194	7
Brown Basalt	194	196	

RECEIVED

AUG 22 1994

WATER RESOURCES
SALEM, OREGON

Date started 4-10-94 Completed 7-20-94

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____

Signed _____

Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 415

Signed Robert W. Steff

Date _____