

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765 & OAR 690-205-0210)

WELL I.D. LABEL# L 125617
START CARD # 218385
ORIGINAL LOG #

(1) LAND OWNER
First Name Jeffery Owner Well I.D. _____
Last Name HANZLIK
Company _____
Address 55090 SMOCK RD
City Tygh Valley State OR Zip 97063

(2) TYPE OF WORK ☒ New Well ☐ Deepening ☐ Conversion
☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION
Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: _____

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE ☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION Special Standard ☐ (Attach copy)

Depth of Completed Well 880 ft.
BORE HOLE
Dia From To Material From To Amt sacks/lbs
12 0 478 Cement 60 478 216 SUS
8 478 880 Bentonite 0 60 40 SUS
Calculated 880
Calculated _____

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other Cement Bottom up, Bentonite poured
Backfill placed from _____ ft. to _____ ft. Material _____
Filter pack from _____ ft. to _____ ft. Material _____ Size _____
Explosives used: ☐ Yes Type _____ Amount _____

(5a) ABANDONMENT USING UNHYDRATED BENTONITE
Proposed Amount Pounds Actual Amount Pounds

(6) CASING/LINER
Casing Liner Dia + From To Gauge Stl Plstc Wld Thrd
☒ ☐ 8 ☒ 2 478 250 ☒ ☐ ☒ ☐
Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s) _____
Temp casing ☐ Yes Dia _____ From _____ To _____

(7) PERFORATIONS/SCREENS
Screens Type _____ Material _____
Perf/S Casing/Screen Scm/slot Slot # of Tele/
creen Liner Dia From To width length slots pipe size

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian
Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)
75 100% 879 2 HR
Temperature 59 °F Lab analysis ☐ Yes By _____
Water quality concerns? ☐ Yes (describe below) TDS amount 103 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)
County Wasco Twp 4 S N/S Range 12 E E/W WM
Sec 33 SE 1/4 of the 9E NW 1/4 Tax Lot 5005
Tax Map Number _____ Lot _____
Lat _____ or 45.18050000 DMS or DD
Long _____ or -121.31075000 DMS or DD
☒ Street address of well ☐ Nearest address

55090 SMOCK RD. TYGH VALLEY OR 97063

(10) STATIC WATER LEVEL
Date SWL(psi) + SWL(ft)
Existing Well / Pre-Alteration _____
Completed Well 5-20-23 481
Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES Depth water was first found 500
SWL Date From To Est Flow SWL(psi) + SWL(ft)
5-20-23 500 880 _____ 481

(11) WELL LOG Ground Elevation _____
Material From To
Soil 0 4
Hard Grey 4 25
Hard Grey Red 25 60
No circulation 60 63
Hard 63 500
Soft water bearing 500 880

RECEIVED
JUL 19 2023
OWRD

Date Started 6-5-22 Completed 5-20-23

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
License Number _____ Date _____
Signed James Hilberts

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
License Number 1782 Date 5-20-23
Signed Joel
Contact Info (optional) _____

**STATE OF OREGON
WELL LOCATION MAP**

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.1805 Datum: WGS84

Longitude: -121.31075

Township/Range/Section/Quarter-Quarter Section:

WM 4S 12E 33 SENW

Address of Well:

55090 SMOCK RD, TYGH VALLEY, OR 97063

Well Label: L125617

Well Log: WASC 52902

Printed: July 27, 2023

DISCLAIMER: This map is intended to represent the approximate location of the well as provided by the land owner, well driller or OWRD staff. It is not intended to be construed as survey accurate in any manner.

Generated by OWRD

