

WAS WASH 11590 RECEIVED
011590 JUN 27 1966

2/1w-10 (E)

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the
STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT
STATE OF OREGON
(Please type or print)

State Well No. ~~Well No. 4~~
State Permit No. _____

(1) OWNER:
Name Tigard Water District
Address 8841 S.W. COMMERCIAL ST.
TIGARD OREGON 97223

(2) LOCATION OF WELL:
County WASHINGTON Driller's well number A4
1/4 NW 1/4 Section 10 T. 2S R. 1W W.M.
Bearing and distance from section or subdivision corner
North of S.W. Bend West of S.W. Pacific
Highway near the King City Development
Well # 4

(3) TYPE OF WORK (check):
New Well Deepening Reconditioning Abandon
If abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):
Domestic Industrial Municipal
Irrigation Test Well Other
(5) TYPE OF WELL:
Rotary Driven
Cable Jetted
Dug Bored

(6) CASING INSTALLED:
242" Diam. from _____ ft. to _____ ft. Gage _____
12" Diam. from 0 ft. to 242 ft. Gage 330

(7) PERFORATIONS:
Perforated? Yes No
Type of perforator used _____
Size of perforations _____ in. by _____ in.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(8) SCREENS:
Well screen installed? Yes No
Manufacturer's Name _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(9) CONSTRUCTION:
Well seal—Material used in seal Cement, sand & gravel
Depth of seal 242 ft. Was a packer used? no
Diameter of well bore to bottom of seal 16 in.
Were any loose strata cemented off? Yes No Depth _____
Was a drive shoe used? Yes No
Was well gravel packed? Yes No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.
Did any strata contain unusable water? Yes No
Type of water? _____ depth of strata _____
Method of sealing strata off _____

(10) WATER LEVELS:
Static level 257 ft. below land surface Date _____
Artesian pressure _____ lbs. per square inch Date _____

(11) WELL TESTS:
Drawdown is amount water level is lowered below static level
Was a pump test made? Yes No If yes, by whom?
Yield: 250 gal./min. with 33 ft. drawdown after 8 hrs.
" 303 " 60 " 8 "
" 360 " 173 " 8 "
Bailer test _____ gal./min. with _____ ft. drawdown after _____ hrs.
Artesian flow _____ g.p.m. Date _____
Temperature of water 56 Was a chemical analysis made? Yes No

(12) WELL LOG:
Diameter of well below casing 12"
Depth drilled 725 ft. Depth of completed well 725 ft.
Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Clay, brown w/grey rock	0	25
Clay & broken rock	25	71
Rock, black	71	103
Rock, brown soft	103	111
Rock, red black	111	141
Clay, red	141	146
Rock, brown soft	146	161
Rock, black hard	161	210
Rock, blue	210	242
Rock, brown	242	320
Rock, red	320	360
Rock, brown	360	389
Rock, red	389	421
Rock, brown	421	429
Rock, blue	429	436
Clay, brown	436	438
Rock, brown	438	460
Rock, blue	460	488
Rock, black, softer	488	500
Rock, blue	500	585
Rock, blue, hard	585	688
Rock, black, coarse	688	695
Rock, brown, reddish(w.brg)	695	712
Basalt, grey, hard	712	725

Work started Feb. 1st. 1966 Completed Aug. 9 19 66
Date well drilling machine moved off of well Aug. 15 19 66

(13) PUMP:
Manufacturer's Name _____
Type: _____ H.P. _____
Water Well Contractor's Certification:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
NAME HAAKON BOTTNER DRILLING COMPANY
(Person, firm or corporation) (Type or print)
Address 3424 S.E. 174th. AVENUE
PORTLAND, OREGON 97236
Drilling Machine Operator's License No. 246 & 380
[Signed] Haakon Bottner
(Water Well Contractor)
Contractor's License No. 109 Date _____, 19 _____



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for
Well ID Number

RECEIVED

MAY 09 2012

WATER RESOURCES DEPT
SALEM, OREGON

Do not complete if the well already has a Well I.D Number.

I. OWNER INFORMATION

Current Owner Name (please print): City of Tigard
Mailing Address: 13125 SW Hall Blvd.
City: Tigard State: Oregon Zip: 97223
Mailing Address (to send Well I.D.): Aaron Beattie, City of Tigard Public Works Department, 13125 SW Hall Blvd.
City: Tigard State: Oregon Zip: 97223

II. WELL INFORMATION (Do not complete this section if the well report is attached.)

City of Tigard Well 4

Township: 2 South (North/South) Range: 1 West (East/West) Section: 10
Tax Lot: 2S110CB00300 County: Washington NW 1/4 SW 1/4
Street Address of Well: 15055 SW 122nd Avenue City: Tigard
Owner at time the well was constructed, (if known): Tigard Water District
If the property had a different street address in the past: N/A

III. GENERAL WELL INFORMATION (Do not complete this section if the well report is attached) WASH 11590 & 11591

Use of Well (domestic, irrigation, commercial, industrial, monitoring):
Date Well Constructed: Total Well Depth: Casing Diameter:
Other Information:

SUBMITTED BY (please print):
PHONE: FAX:

Send application to Oregon Water Resources Department; 725 Summer St NE, Suite A; Salem, Oregon 97301-1266; fax (503) 986-0902. Applications are processed and Well I.D. Numbers are mailed every Wednesday.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

Well Log Number:

Well Identification #:

WASH 11590

109497