

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97314
within 30 days from the date
of well completion.

WASH WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

RECEIVED
MAR 7 1973

State Well No.

State Permit No.

25/1W-34

(1) OWNER:

Name T. D. SHARMAN
Address 24135 SW GRAHAM'S FERRY ROAD
SHERWOOD, ORE.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 82 ft. Gage 350
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yard: gal./min. with ft. drawdown after hrs.

Bailer test 26 gal./min. with 6 ft. drawdown after 1 1/2 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT GROUT
Well sealed from land surface to 30 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 8 sacks
Number of sacks of bentonite used in well seal sacks
Brand name of bentonite
Number of pounds of bentonite per 100 gallons
of water lbs./100 gals.
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County WASH Driller's well number 5435
SE 1/4 SE 1/4 Section 34 T. 25 R. 1W W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 114 ft.
Static level 61 ft. below land surface. Date 2/27/73
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6
Depth drilled 164 ft. Depth of completed well 164 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	3	
RED CLAY	3	22	
BROWN CLAY	22	64	
BROKEN BROWN ROCK	64	72	
MED. HARD GREY BASALT	72	114	
POROUS BROWN ROCK	114	125	
MED. HARD GREY BASALT	125	141	
POROUS GREY BASALT	141	160	
MED HARD GREY BASALT	160	164	

Work started FEB 26 1973 Completed FEB 27 1973

Date well drilling machine moved off of well FEB 27 1973

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Edward S. Smith Date 3/5 1973
(Drilling Machine Operator)

Drilling Machine Operator's License No. 564

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name R. J. STRASSER DRILLING CO
(Person, firm or corporation) (Type or print)

Address 8110 SE SUNSET LANE PORTLAND ORE.

[Signed] Robert L. Strasser
(Water Well Contractor)

Contractor's License No. 10 Date MAR 5 1973