

# NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON

within 30 days from the date of well completion.

WASH  
012476

## WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

RECEIVED

State Well No.

252W-86a

APR 7 1978

State Permit No.

WATER RESOURCES DEPT.

### (1) OWNER:

Name Ralph Butcher  
Address R#2 Box 147A, Hillsboro, Oregon 97123

### (2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐  
If abandonment, describe material and procedure in Item 12.

### (3) TYPE OF WELL:

Rotary ☐ Driven ☐  
Cable ☒ Jetted ☐  
Dug ☐ Bored ☐

### (4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐  
Irrigation ☐ Test Well ☐ Other ☐

### (5) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 262 ft. Gage 250  
" Diam. from ft. to ft. Gage  
" Diam. from ft. to ft. Gage

### (6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.  
perforations from ft. to ft.  
perforations from ft. to ft.  
perforations from ft. to ft.

### (7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name  
Type Model No.  
Diam. Slot size Set from ft. to ft.  
Diam. Slot size Set from ft. to ft.

### (8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.  
" " " "  
" " " "  
Bailer test 12 gal./min. with 120 ft. drawdown after 2 hrs.  
Artesian flow g.p.m.

### (9) CONSTRUCTION:

Well seal—Material used Cement Grout  
Well sealed from land surface to 20 ft.  
Diameter of well bore to bottom of seal 9 in.  
Diameter of well bore below seal 6 in.  
Number of sacks of cement used in well seal 12 sacks  
Number of sacks of bentonite used in well seal sacks  
Brand name of bentonite  
Number of pounds of bentonite per 100 gallons of water lbs./100 gals.  
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.  
Did any strata contain unusable water? ☐ Yes ☒ No  
Type of water? depth of strata  
Method of sealing strata off  
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.  
Gravel placed from ft. to ft.

### (10) LOCATION OF WELL:

County Washington Driller's well number 242  
N.E. 1/4 NW 1/4 Section 8 T. 2, S. R. 2, W. W.M.

Bearing and distance from section or subdivision corner

2595' East - 820' South of NW Corner Sec. 8

### (11) WATER LEVEL: Completed well.

Depth at which water was first found 289 ft.  
Static level 37 ft. below land surface. Date 4/3/78  
Artesian pressure lbs. per square inch. Date

### (12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 289 ft. Depth of completed well 289 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

| MATERIAL               | From | To   | SWL |
|------------------------|------|------|-----|
| clay - brown           | 0'   | 47'  |     |
| clay - blue, with sand | 47'  | 110' |     |
| clay - blue            | 110' | 134' |     |
| clay - brown           | 134' | 156' |     |
| clay - gray            | 156' | 165' |     |
| clay - brown           | 165' | 170' |     |
| clay - red             | 170' | 173' |     |
| clay - brown           | 173' | 208' |     |
| clay - red             | 208' | 220' |     |
| clay - brown           | 220' | 240' |     |
| Sandstone brown        | 240' | 264' |     |
| Rock - gray with gray  |      |      |     |
| clay - sandy           | 264' | 289' | 37' |

Work started 3/22/78 Completed 4/3/78  
Date well drilling machine moved off of well 4/3/78

### Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Jack Barron Date 4/15, 1978  
(Drilling Machine Operator)

Drilling Machine Operator's License No. 165

### Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Jack Barron  
(Person, firm or corporation) (Type or print)

Address 16425 SW Hart, Beaverton, Oregon

[Signed] Jack Barron  
(Water Well Contractor)

Contractor's License No. 59 Date 4/15, 1978