

APR 13 1990

STATE OF OREGON
WATER WELL REPORT
 (as required by ORS 537.765)

WATER RESOURCES DEPT. **WASH# 013**
 SALEM, OREGON

(START CARD) # **2s/2w/22cc**
 19637

(1) OWNER:Name Mike & Laura KaiserWell Number: 633Address 183 S.E. 6thCity HillsboroState ORZip 97123**(2) TYPE OF WORK:**
☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon
(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other _____**(4) PROPOSED USE:**
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation

☐ Thermal ☐ Injection ☐ Other _____
(5) BORE HOLE CONSTRUCTION:Special Construction approval Yes ☐ No ☒ Depth of Completed Well 505 ft.Explosives used Yes ☐ No ☒ Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10"	0'	79'	Cement	0'	79'	20 Sacks
6"	79'	505'				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	+1'	80'	.025	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s) 505'**(7) PERFORATIONS/SCREENS:**☐ Perforations

Method _____

☐ Screens

Type _____

Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour☐ Pump☐ Bailer☒ Air☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
20 GPM		505'	1 hr.

Temperature of water 53° Depth Artesian Flow Found _____Was a water analysis done? ☐ Yes By whom _____Did any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:County Washington Latitude _____ Longitude _____Township 2-S N or S, Range 2-W E or W, WM.Section 22 SW 1/4 SW 1/4Tax Lot 800 Lot _____ Block _____ Subdivision _____Street Address of Well (or nearest address) Lower Scholls/Mt. Home Road**(10) STATIC WATER LEVEL:**260 ft. below land surface.Date 3/28/90

Artesian pressure _____ lb. per square inch.

Date _____

(11) WATER BEARING ZONES:Depth at which water was first found 320'

From	To	Estimated Flow Rate	SWL
320'	335'	15 GPM	n/a
495'	500'	5 GPM	260'

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
Top Soil	0	2	
Red/Brown Clay	2	20	
Soft Decomp. Rock & Clay	20	25	
M.H. Brown Decomp. Basalt	25	35	
Soft Brwn. Decomp. Basalt	35	55	
M.H. Brown Decomp. Basalt	55	70	
Hard Gray Basalt	70	90	
Hard Blk. & Brwn. Basalt	90	120	
Hard Brown Basalt	120	140	
Hard Gray/Brown Basalt	140	160	
Hard Gray Basalt	160	255	
M.H. Gr/Brwn. Basalt	255	265	
M.H. Brown Basalt	265	280	
Hard Gray Basalt	280	320	
M.H. Gray/Brwn. Basalt	320	335	
M.H. Gray Basalt	335	340	
Hard Gray Basalt	340	415	
M.H. Gr/Brwn. Basalt	415	440	
Hard Gray Basalt	440	495	
Med. Hard Gray/Brwn. Basalt	495	500	
Hard Gray Basalt	500	505	

Date started 3/23/90Completed 3/28/90**(unbonded) Water Well Constructor Certification:**

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number _____

Signed _____

Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 645Signed [Signature]Date 4/11/90