

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

RECEIVED
JUL 9 1969

WATER WELL REPORT WASH

STATE ENGINEER, SALEM, OREGON 97301

STATE OF OREGON

State Well No. 3/1W-2d

within 30 days from the date of well completion.

STATE ENGINEER (Please type or print)
SALEM OREGON

(Do not write above this line)

013633

State Permit No.

(1) OWNER:

Name Burns Bros. Truck Stations
Address 621 S. E. Union Ave., Portland, Or.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☒
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
10" Diam. from 0 ft. to 59 ft. Gage 0.250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations	in. by	in.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 40 ft. below land surface Date 6-20-69
man pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Steinman Bros.

Yield:	gal./min. with	ft. drawdown after	hrs.
200	55	2	
150	40	4	
140	19	2	

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 52° Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Cement and Bentonite
Depth of seal 58 ft.
Diameter of well bore to bottom of seal 14 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☐ Yes ☒ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Washington Driller's well number 35-69
1/4 SE 1/4 Section 2 T. 3S R. 1W W.M.

Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 10"

Depth drilled 387 ft. Depth of completed well 387 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Clay, brown	0	12	
Clay, greenish brown	12	29	
Rock, decomposed brown	29	49	
Rock, grey brown	49	70	
Rock, grey, hard	70	81	
Rock, grey, soft	81	103	
Conglomerate, brown	103	125	
Rock, grey, hard	125	143	
Rock, brown, soft	143	163	
Rock, grey, hard	163	216	
Rock, brown, soft	216	223	
Rock, grey, hard	223	282	
Rock, brown, soft	282	290	
Rock, grey, hard	290	326	
Rock, red, soft	326	336	
Rock, brown, hard	336	359	
Rock, grey, hard	359	387	40

Work started Apr. 28 1969 Completed June 20 1969

Date well drilling machine moved off of well June 25 1969

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Jack Davis Date June 27, 1969
(Drilling Machine Operator)

Drilling Machine Operator's License No. 67

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Steinman Bros.
(Person, firm or corporation) (Type or print)

Address Milwaukie, Or. 97222

[Signed] Robert E. McConnell
(Water Well Contractor)

Contractor's License No. I Date June 27, 1969

Note:

The card sent in on this on April 25, 1969 was made out for the Hunt Building Marts, P. O. Box 9368, El Paso, Texas. The well, our #35-69 is to be registered to Burns Bros. Truck Stations, 621 S. E. Union Ave., Portland, Or.

Noted
RECEIVED
JUL 9 1969
STATE ENGINEER
SALEM