

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

PLEASE TYPE or PRINT IN INK

(for official use only)

(1) OWNER:

Name Dwight Mc Cul WATER RESOURCES DEPT
Address 2247 Maple St SALEM, OREGON
City Forest Grove State OR 97116

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Thermal: ☐ Withdrawal ☐ Reinjection ☐
Cable ☐ Bored ☐ Other: ☐ Piezometric ☐ Grounding ☐ Test ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
6" Diam. from +1 ft. to 117 ft. Gauge .250

LINER INSTALLED:

Steel ☐ Plastic ☐
Threaded ☐ Welded ☐
" Diam. from " ft. to " ft. Gauge "

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No
Size of perforations in. by in.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Diam. Slot Size Set from " ft. to " ft.
Diam. Slot Size Set from " ft. to " ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☐ Yes ☒ No If yes, by whom?
Yield: gal./min. with " ft. drawdown after " hrs.
Air test 1.5 gal./min. with drill stem at 85 ft. 1 hrs.
Bailer test gal./min. with " ft. drawdown after " hrs.
Artesian flow g.p.m.

Temperature of water 55.5 Depth artesian flow encountered " ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒
Well seal—Material used cement
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 12 in.
Diameter of well bore below seal 6 in.
Amount of sealing material 6 sacks ☒ pounds ☐
How was cement grout placed? Pumped
Was pump installed? No Type " HP " Depth " ft.
Was a drive shoe used? ☒ Yes ☐ No Plugs " Size: location " ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? " depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: " ft.
Gravel placed from " ft. to " ft.

(10) LOCATION OF WELL by legal description:

County Wash NW 1/4 SW 1/4 of Section 32 of
Township 1N, Range 3W, WM.
(Township is North or South) (Range is East or West)
Tax Lot " Lot " Block " Subdivision "

MAILING ADDRESS OF WELL (or nearest address)

(11) WATER LEVEL of COMPLETED WELL:

Depth at which water was first found 119 ft.
Static level 1.5 ft. below land surface. Date 7-31-85
Artesian pressure lbs. per square inch. Date "

(12) WELL LOG:

Diameter of well below casing 6
Depth drilled 124 ft. Depth of completed well 124 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown Soil	0	2	
Brown Clay	2	25	
Blue Sand	25	45	
Blue Clay	45	80	
Brown Clay	80	95	
Brown sand	95	100	
Tan clay	100	119	
Brown sand + gravel	119	124	1.5

Date work started 7-23-85 completed 7-31-85
Date well drilling machine moved off of well 7-31 1985

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] " Date " 19 "

(bonded) Water Well Constructor Certification:

Bond 32740 Issued by: Are auto clms
(number) (Surety Company Name)
On behalf of Joseph Trussell
(type or print name of Water Well Constructor)

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief:

(Signed) Joseph Trussell
(Water Well Constructor)
(Dated) 7-31-85

NOTICE TO WATER WELL CONSTRUCTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*46866