

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

RECEIVED

JUN 4 1974

State Well No.

2N/5W-28

STATE ENGINEER

SALEM, OREGON

State Permit No.

(1) OWNER:

Name

Address

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☒ Welded ☐

6" Diam. from 0 ft. to 118 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations

in. by

in.

perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

Bailer test 8 gal./min. with 30 ft. drawdown after 2 hrs.

Artesian flow g.p.m.

Temperature of water 53 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used

Well sealed from land surface to 118 ft.

Diameter of well bore to bottom of seal 9 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal sacks

Number of sacks of bentonite used in well seal 2 sacks

Brand name of bentonite National

Number of pounds of bentonite per 100 gallons

of water lbs./100 gals.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Washington

Driller's well number

1/4

1/4

Section 28

T. 2N

R.

3 W

W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found

161

ft.

Static level

95

ft. below land surface. Date

Artesian pressure

lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 173 ft. Depth of completed well 173 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil	0	2	
Yellow clay	2	12	
Red "	12	35	
Soft sand rock	35	90	
" Brown "	90	115	
Blue "	115	135	
Brown "	135	145	
Blue "	145	160	
Brown "	160	173	78

Work started 4-27-1974 Completed 5-3-1974

Date well drilling machine moved off of well 5-6-1974

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] E. M. Gregory Date 6-1-1974

(Drilling Machine Operator)

Drilling Machine Operator's License No. 207

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name E. M. Gregory Drilling Co.

(Person, firm or corporation)

(Type or print)

Address

Rt. 1, Box 159

Banks, Oregon 97106

[Signed] E. M. Gregory

(Water Well Contractor)

Contractor's License No. 99 Date 6-1-1974