

RECEIVED

JUL 23 1996

WELL ID #

L 07008

STATE OF OREGON WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

WATER RESOURCES DEPT.

Instructions for completing this report are on the back of this form.

(1) OWNER:

Well Number

Name Raymond Rogers
Address 22022 NW Dairy Cr Rd
City Cornelius OR State OR Zip 97113

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well _____ ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10	0	38	Bentonite	0	30	15
6	38	140	Cement	30	38	3

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6	15"	40"	250	☒	☐	☒	☐
Liner: 4"	3'	140'	160	☐	☒	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

From		To		Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
100	140	18"	28"					☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
60		140	1 hr.
60		110	1

Temperature of water 54 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County WASHINGTON Latitude _____ Longitude _____
Township 2N N or S Range 3W E or W. WM.
Section 4 NW 1/4 SW 1/4
Tax Lot 1401 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 22022 NW Dairy Cr Rd
Cornelius OR 97113

(10) STATIC WATER LEVEL:

32 ft. below land surface. Date 7-20-96
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 50

From	To	Estimated Flow Rate	SWL
50	135	60	

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Top Soil	0	1	
Brown Clay	1	25	
Gray Clay	25	45	
Gray Sand Stone	45	140	

Date started 7-19-96 Completed 7-20-96

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____

Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number _____

Signed Cyril Van derhey Date _____

ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER