

WASH
51664

JAN - 8 1997

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPT. (START CARD) # 92721
SALEM, OREGON

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number _____
Name LEE HODGES
Address 6250 NW JACKSON SCHOOL RD.
City HILLSBORO State OR Zip 97124

(2) TYPE OF WORK
 New Well Deepening Alteration (repair/recondition) Abandonment

(3) DRILL METHOD:
 Rotary Air Rotary Mud Cable Auger
 Other _____

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 910 ft.
Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	823	HOLEPLUG	0	40	35 SKS
			DRILL GEL	40	714	
			CEMENT	714	823	30 SKS
6"	823	910				

How was seal placed: Method A B C D E
 Other POURED INTO ANNULAR
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	+1	823	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:					<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

		Method		Material			
		Type		Tele/pipe size	Casing	Liner	
From	To	Slot size	Number	Diameter			
					<input type="checkbox"/>	<input type="checkbox"/>	
					<input type="checkbox"/>	<input type="checkbox"/>	
					<input type="checkbox"/>	<input type="checkbox"/>	
					<input type="checkbox"/>	<input type="checkbox"/>	
					<input type="checkbox"/>	<input type="checkbox"/>	

(8) WELL TESTS: Minimum testing time is 1 hour

<input type="checkbox"/> Pump	<input type="checkbox"/> Bailer	<input checked="" type="checkbox"/> Air	<input type="checkbox"/> Flowing Artesian
Yield gal/min	Drawdown	Drill stem at	Time
75		200'	1 hr.
110		300'	
150		500'	

Temperature of water 61° F Depth Artesian Flow Found _____
Was a water analysis done? Yes By whom AMJ
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Washington Latitude _____ Longitude _____
Township 1N N or S Range 2W E or W. WM.
Section 17 SW 1/4 SW 1/4
Tax Lot 301 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 6250 NW Jackson School Rd., Hillsboro, OR

(10) STATIC WATER LEVEL:
50 ft. below land surface. Date 12/31/96
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 850

From	To	Estimated Flow Rate	SWL
850	908	150 GPM	50

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Topsoil	0	2	
Soft brown clay	2	13	
Soft gray silty clay	13	63	
Sticky gray clay	63	82	
Sticky gray-brown clay	82	145	
Soft blue-gray clay	145	206	
Sticky gray clay	206	283	
Soft gray-brown clay	283	318	
Sticky brown clay	318	377	
Sticky blue-gray clay	377	438	
Soft dark gray clay	438	484	
Sticky blue-gray clay	484	750	
Wood	750	763	
Sticky gray clay	763	785	
Soft brown clay	785	813	
Hard gray-black basalt, occ. brown interbed	813	910	50

Date started 11/28/96 Completed 12/31/96
(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
WWC Number 1266
Signed [Signature] Date 12/31/96