

RECEIVED

WASH. 52021

APR - 4 1997

WELL I.D.# 137035

108796 LOST!

STATE OF OREGON WATER SUPPLY WELL REPORT (as required by ORS 537.765) WATER RESOURCES DEPT.

(START CARD)# 88866

Instructions for completing this report are on page 2 of this form.

(1) OWNER: Well Number 97-006 Name Lynn Hatch Address 14135 SW 114th City Tigard State OR Zip 97224

(2) TYPE OF WORK [X] New Well [ ] Deepening [ ] Alteration (repair/recondition) [ ] Abandonment

(3) DRILL METHOD: [X] Rotary Air [ ] Rotary Mud [ ] Cable [ ] Auger [ ] Other

(4) PROPOSED USE: [X] Domestic [ ] Community [ ] Industrial [ ] Irrigation [ ] Thermal [ ] Injection [ ] Livestock [ ] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval [ ] Yes [X] No Depth of Completed Well 315 ft. Explosives used [ ] Yes [X] No Type Amount

Table with columns: HOLE Diameter, From, To, Material, SEAL From, To, Sacks or pounds. Rows include 10" cement bent and 6" bent.

How was seal placed: Method [ ] A [ ] B [X] C [ ] D [ ] E [X] Other bent poured dry and hydrated Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Rows for Casing (6") and Liner (4").

(7) PERFORATIONS/SCREENS: [X] Perforations Method saw cut [ ] Screens Type Material. Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner.

(8) WELL TESTS: Minimum testing time is 1 hour [ ] Pump [ ] Bailer [X] Air [ ] Artesian. Yield gal/min 56, Drawdown n/a, Drill stem at 305, Time 1 hr. Temperature of water 54° Depth Artesian Flow Found. Was a water analysis done? [ ] Yes By whom. Did any strata contain water not suitable for intended use? [ ] Too little. [ ] Salty [ ] Muddy [ ] Odor [ ] Colored [ ] Other. Depth of strata:

(9) LOCATION OF WELL by legal description: County Washington Latitude Longitude Township 2S N or S Range 1W E or W. WM. Section 35 NW 1/4 SE 1/4 Tax Lot 302 Lot Block Subdivision Street Address of Well (or nearest address) 2350 SW Boones Ferry Rd, Tualatin, Oregon

(10) STATIC WATER LEVEL: 191 ft. below land surface. Date 3-27-97 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: 21 Depth at which water was first found

Table with columns: From, To, Estimated Flow Rate, SWL. Rows: 21-65 less 10 gpm 18; 256-260 6 gpm 191; 295-313 50 gpm 191.

(12) WELL LOG: Ground Elevation

Table with columns: Material, From, To, SWL. Rows: topsoil (0-2), clay brown (2-21), rock decomp brown (21-32), basalt decomp sandstone conglomerate (32-65), basalt grey medium (65-116), basalt grey hard (116-180), clay brown (180-181), basalt grey/brown with claystone yellow (181-198), basalt grey/brown with soapstone (198-215), basalt grey medium (215-256), basalt brown/grey decomp (256-260), basalt brown/grey med (260-295), lava red (295-300), basalt vesic multicolors with lava red (300-313), basalt grey medium (313-315).

Date started 3-25-97 Completed 3-27-97

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief. ARROW DRILLING 538-4422 WWC Number Signed Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief. Signed Date WWC Number 1483



Oregon Water Resources Department  
 725 Summer Street NE, Suite A  
 Salem Oregon 97301  
 (503) 986-0900  
 www.oregon.gov/owrd

# Application for Well ID Number

Replacement tag

RECEIVED

JAN 13 2020

Do not complete if the well already has a Well Identification Number.

**I. OWNER INFORMATION**

Current Owner Name (please print): Horizon Community Church  
 Mailing Address: PO Box 2690 **OWRD**  
 City, State, Zip: Tualatin, OR 97062  
 Mail Well ID to:  SAME AS ABOVE  In Care Of (C/O)  
 Name & Address: \_\_\_\_\_  
 City, State, Zip: \_\_\_\_\_

**II. WELL LOCATION INFORMATION** (Please fill out as completely as possible)

Township: 2S (North / South) Range: 1W (East / West) Section: 35 SW 1/4 of the SE 1/4  
 Tax Lot (usually last 3-5 numbers of Tax Map #): 106 County Washington  
 GPS Coordinates: \_\_\_\_\_  
 Street Address of Well, City: 23370 Sw Boones Ferry Rd Tualatin  
 If the property had a different street address in the past: 23560 Sw Boones Ferry Rd Tualatin  
Original Tax Lot 302

**III. GENERAL WELL INFORMATION** (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Per well log WASH 52021 Domestic  
 Date Well Constructed (or property built): 3-27-1997 Total Well Depth: 315 feet Casing Diameter: 6 inch  
 Owner at time the well was constructed (if known): Lynn Hatch Well Report # (if known): WASH 52021  
 Other Information: Replacement of well tag L-08796 - lost!

SUBMITTED BY (please print): SCOTT PLATT  
 PHONE: 503-729-0173 EMAIL &/or FAX: splatt@horizonlife.org

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902.  
 Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

\*Replacement #

For Official Use Only by the Oregon Water Resources Department:		
Received Date: <u>1-13-2020</u>	Well Report Number: <u>WASH 52021</u>	Well Identification #: <u>L-137035</u>