

JUN 3 0 1997

State of Oregon WATER RESOURCES DEPT.
WATER WELL REPORT (as required by ORS 337.763) SALEM, OREGON

Page 1 of 1

WASH
52304State Well ID L13482
Start Card # 85866

(1) OWNER: Well No. 1684
Name MUNRO PITT
Address 1885 PRIMROSE LN
City FOREST GROVE St OR Zip 97116

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: FARM

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 301 ft
Explosives used NO Type Amount

HOLE			SEAL			
Diam.	From	To	Material	From	To	Amount
10	0	48	BENTONITE	0	48	21 SAX
6	48	301				

Seal placement method POURED/TAMPED

Backfill: from ___ ft to ___ ft Material

Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

Diam.	From	To	Gauge	Material	Connection
Casing 6	+2	48	.25	STEEL	WELDED

Diam.	From	To	Material	Connection
Liner 4	3	301	SDR26 PLASTIC	WELDED

Final Location of shoe(s) NO SHOE

(7) PERFORATIONS/SCREENS:

[X] Perf. Method ELECTRIC SAW

[] Screens Type Material

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
100	120	6"	32			LINER
281	301	6"	32			LINER

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
5		281	1 hr.
5		301	4

Temperature of water 53 Depth Artesian Flow Found

Was water analysis done? NO By whom

Reason for water not suitable for use

Depth of strata

(9) LOCATION OF WELL by legal description:

County WASHINGTON Lat. ' ' ' Long. ' ' '
Township 1 S Range 4 W WM.
Section 27 NE 1/4 SE 1/4
Tax Lot 1500 Lot Block Subdivision
Street Address of Well (or nearest Address)
9449 SW OLD HWY 47 FOREST GROVE, OR

(10) STATIC WATER LEVEL:

74 ft. below land surface. Date 06/25/97
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 85		Est Flow Rate	SWL
From	To		
85	87	3	74
172	173	2	74

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	3	
TAN CLAY	3	9	
RED CLAY	9	30	
BROWN CLAY	30	37	
GRAY SANDSTONE/OCC SILTSTONE	37	85	
COARSE SANDSTONE, BROKEN	85	87	74
GRAY SANDSTONE/OCC SILTSTONE	87	172	
GRAY SANDSTONE, HARD/FRACTURED	172	173	74
GRAY SANDSTONE/OCC SILTSTONE	173	301	

DAVE PAYSINGER, BLUE WATER DRILLING CO.
DAYTON, OR. 97114

Date started 06/24/96

Completed 06/25/97

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David L. Paysinger* WWC Number 1438
Date 06/25/97