

RECEIVED

Wash
52339

JUL 10 1997

WELL I.D.# L14736

STATE OF OREGON WATER SUPPLY WELL REPORT (as required by ORS 537.765)

WATER RESOURCES DEPT.
OREGON

(START CARD) # 098106

Instructions for completing this report are on the last page of this form.

(1) OWNER: Mr + Mrs Barry Kraxberger
Name Mr + Mrs Barry Kraxberger
Address P.O. Box 2073
City Beaumont, OR State OR Zip 97005

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 275 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
10 1/2"	0	98	Cement	48	98	20 Sacks
			Beaumont	0	48	25 Sacks lb
6"	98	275				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☒ Other Beaumont placed top to bottom slowly.
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+2	98	250	☒	☐	☒	☐
Liner: 4"	15	275	160	☒	☒	☒	☐

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Electric drill
☐ Screens Type 3/8" circular Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
215	275		180	7/8" circular		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailor ☒ Air ☐ Flowing Artesian

Yield gal/min 40 Drawdown _____ Drill stem at _____ Time 1 hr.

Temperature of water 52° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Washington Latitude _____ Longitude _____
Township 25 N or S Range 2W E or W. WM.
Section 17 SE 1/4 SE 1/4
Tax Lot 2217 Lot 2500 Block _____ Subdivision _____
Street Address of Well (or nearest address) 17935 S.W. Highway 219 Hillsboro, OR

(10) STATIC WATER LEVEL:
144 ft. below land surface. Date June 25, 97
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 150 ft 5 G.P.M.

From	To	Estimated Flow Rate	SWL
150	152	10 G.P.M.	
175	176	10 G.P.M.	
230	235	20 G.P.M.	

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Topsoil	0	3	
Brown & yellow clays	3	58	
Reddish silty clay	58	85	
Dark green & brown basalt	85	90	
Medium Hard blue basalt	90	150	
Blue & brown basalt with fractured layers	150	275	
Unstable basalt	275	291	

Date started June 19, 97 Completed June 25, 97
(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____ Date _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed June A. Wilcox WWC Number 1765 Date June 28, 97