

WATER RESOURCES DEPT.
SALEM, OREGON

OCT 06 2000

RECEIVED

(1) OWNER: Well No. 2005
Name CHERRY HILL LLC
Address 1885 PRIMROSE LANE
City FOREST GROVE St OR Zip 97116

(2) TYPE OF WORK: NEW WELL
(3) DRILL METHOD: ROTARY AIR
(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO _____ Depth of Compl. Well 100 ft
Explosives used NO _____ Type _____ Amount _____
HOLE SEAL
Diam. From To Material From To Amount
10 0 38 BENTONITE CHIP 0 38 19 SAX
6 38 100 _____

Seal placement method POURED/PROBED
Backfill: from _____ ft to _____ ft Material _____
Gravel: from _____ ft to _____ ft Size _____

(6) CASING/LINER:
Casing 6 0 38 .25 STEEL WELDED
Liner 4 0 100 SDR26 PLASTIC WELDED
Final Location of shoe(s) 38

(7) PERFORATIONS/SCREENS:
[X] Perf. Method ELECTRIC SAW
[] Screens Type _____ Material _____
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
80 100 .1X7" 36 _____ LINER

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
100 _____ 100 1 hr.
100 _____ 80 1
100 _____ 75 1
Temperature of water 53F Depth Artesian Flow Found _____
Was water analysis done? NO By whom _____
Reason for water not suitable for use _____
Depth of strata _____

(9) LOCATION OF WELL by legal description:
County WASHINGTON Lat. ' ' ' Long. ' ' '
Township 1 S Range 4 W WM.
Section 26 NW 1/4 SW 1/4
Tax Lot 1500 Lot Block Subdivision
Street Address of Well (or nearest Address)
9449 SW OLD HWY 47 FOREST GROVE, OR

(10) STATIC WATER LEVEL:
+1.5 ft. below land surface. Date 09/27/00
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 53
From To Est Flow Rate SWL
53 85 100+ +1.5

(12) WELL LOG:
Material Ground elevation From To SWL
TOP SOIL 0 4
CLAY, BROWN 4 13
CLAY, BLUE/DENSE 13 20
CLAY, GREEN W/LIGHT SAND 20 25
SHALE, BROWN/HARD 25 31
SANDSTONE, BLUE/GRAY/HARD 31 53
SANDSTONE, VERY HARD/FRACTURED OR BROKEN 53 85 +1.5
SANDSTONE, HARD GRAY 85 100

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878
Date started 09/27/00 Completed 09/27/00

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed *David S. Paysinger* WWC Number 1438
Date 09/27/00